


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well:	County <b>Kearny</b>	Township name <b>Southside</b>	Fraction <b>NE of NW 1/4</b>	Section number <b>4</b>	Town number <b>T26S</b>	Range number <b>R-35-W</b>
Distance and direction from nearest town or city: <b>12 miles South of Deerfield, Kansas.</b>				3 Owner of well: <b>White Enterprises</b> Address: <b>Lakin, Kansas</b>		
Locate with "X" in section below: 				4 Well depth: <b>423</b> ft. Date of completion <b>1-31-75</b> Well diameter <b>26</b> in.		
2 Type and color of material				5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Overburden				6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>		
Fine to Medium Sand & Gravel				7 Casing: Material <b>St.</b> Height: <b>above/below</b> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. Diam. <b>16</b> in. to <b>424</b> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <b>16</b> in. to <b>424</b> ft. depth		
Brown Sandy Clay				8 Screen: <b>Johnson Division</b> Manufacturer <b>Galv.</b> Dia. <b>16"</b> Type <b>100</b> Length <b>20'</b> Set between <b>380</b> ft. and <b>400</b> ft. Perforations: <b>120-160, 300-380, 400-423</b> Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <b>1/2" down</b>		
Fine to Medium Sand & Gravel				9 Static water level: <b>72</b> ft. below land surface Date <b>1-31-75</b>		
Blue & Brown Sandy Clay				10 Pumping level below land surfaces: <b>157</b> ft. after <b>3</b> hrs. pumping <b>1180</b> g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield <b>1200</b> g.p.m.		
Fine to Medium Sand & Gravel (Loose)				11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ____		
Fine to Medium Sand & Gravel (Loose) Clay streaks 10%				12 Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> inches above grade		
Fine to Medium Sand & Gravel (Loose)				13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Clay Puddled Depth: From ____ ft. to ____ ft.		
Brown Sandy Clay				14 Nearest source of possible contamination: ft. ____ Direction ____ Type <b>N/A</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Fine to Medium Sand & Rock (Loose)				15 Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>EMC-Peerless</b> Model number <b>G105884</b> HP <b>100</b> Volts ____ Length of drop pipe <b>160</b> ft. capacity <b>800</b> g.m.p. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Fine to Medium Sand & Gravel (Loose)				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Minter-Wilson Drlg. Co. 208</b> Business name License No. ____ Address <b>Box 493 Garden City, Ks.</b> Signed <b>[Signature]</b> Date <b>3-10-75</b> Authorized representative		
Fine Sand & Clay Streaks (Tight)						
Coarse Gravel						
Yellow Shale, Clay & Rock (use a second sheet if needed)						
16 Remarks: elevation <b>Located near center of 1/4 Section</b> <b>Good Well</b> Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley <b>No other comments!</b> <b>No Possible Contamination</b>						

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5