

DRILLERS TEST LOG

CUSTOMERS NAME Hitch Family Farms DATE 10-13-80
 STREET ADDRESS Box 1054 TEST # 2 E. LOG Yes
 CITY & STATE Garden City, KS DRILLER Mai
 COUNTY Kearny QUARTER SE SECTION 10 TOWNSHIP 26 RANGE 35
 LOCATION _____ Well Location _____

%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level _____	Proposed Well Depth _____
	From	Pay	To			
	0		38	Surface Sand		
	38		46	Brown clay		
	46		108	Sand - fine to med course small to large gravel few clay stks & cemented ledges		
	108		132	Sand - fine to med course small to med gravel & few sandy clay stks		
	132		143	Gray clay		
	143		173	Sand - fine to med course small & few med gravel, brown sandy gray clay stks few cemented ledges		
	173		196	Brown clay few sand stks		
	196		224	Sand - fine to med course small gravel few clay stks		
	224		227	Brown clay		
55	227	13	240	Sand - fine to med course small to med gravel		
40	240	7	247	Sand - fine to med course small gravel & clay stks		
65	247	13	260	Sand - fine to med course small to med gravel loose		
	260		264	Brown Sandy Clay		
55	264	16	280	Sand - fine to med course small to med gravel few sandy clay stks		
35	280	6	286	Sand - fine to med course & brown sandy clay		
60	286	28	314	Sand - fine to med course small to med gravel few sandy clay stks		
55	314	13	327	Sand - fine to med course small gravel few small white clay stks		
	327		335	Brown sandy clay, white clay, sand rock & limerock		
	335		342	Brown clay		
40	342	17	359	Sand - fine & small few med, few clay stks		
	359		379	Brown clay sticky		
20	379	6	385	Sand - fine & small (Hard to catch) clay stks		
	385		405	Brown clay & sand - fine & small		
40	405	17	422	Sand - fine & small few med few brown rock, few clay stks		
poor	422	12	434	Brown & white soapstone, sandstone stks uses water		
very good	434	45	479	Brown sandstone few soapstone stks uses water		
				Added 1/3 sack bran few black rock		
poor	479	11	500	Brown & gray soapstone & brown sandstone, drills very firm		
	500		540	Brown & gray soapstone red clay stks sticky		
fair	540	26	566	Gray sandstone, very hard ledges		
	566		600	Gray shale Hard		
				8 Sacks Quik-Gel		
				Set up North Pit - East		

GARDEN CITY, KS
 Phone 276-3278

HENKLE DRILLING & SUPPLY CO., INC.
 IRRIGATION HEADQUARTERS

SUBLETTE, KS
 Phone 675-4311

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * STOCK WELLS