

DRILLERS TEST LOG

CUSTOMERS NAME	Hitch Family Farms	DATE	3-18-80
STREET ADDRESS	Box 1054	TEST #	1
CITY & STATE	Garden City, KS 67846	DRILLER	Livingston
COUNTY	Kearny	QUARTER	NW
	SECTION 35	TOWNSHIP	26
		RANGE	35

LOCATION 30' north of pivot

#	DRILLED		FOOTAGE	DESCRIPTION OF STRATA	STATIC WATER LEVEL	
	FROM	PAY			PROPOSED WELL DEPTH	
	0		25	SURFACE		
	25		30	BROWN SANDY CLAY		
	30		39	SAND FINE TO MED.		
	39		46	BROWN SANDY CLAY		
	46		50	SAND FINE TO MED.		
	50		69	BROWN CLAY		
	69		116	SAND FINE TO MED. SMALL TO LARGE GRAVEL		
	116		130	BROWN SANDY CLAY & FEW ROCK LEDGES		
	130		158	SAND FINE TO MED. COARSE & BROWN SANDY CLAY		
	158		166	BROWN CLAY		
55	166	24	190	SAND FINE TO MED. COARSE SMALL GRAVEL		
	190		199	BROWN GRAY & BLUE CLAY		
50	199	11	210	SAND FINE TO MED. COARSE SMALL GRAVEL		
	210		221	BROWN SANDY CLAY		
45	221	6	227	SAND FINE TO MED. COARSE		
	227		241	BROWN SANDY CLAY FEW SAND STKS.		
50	241	13	254	SAND FINE TO MED. COARSE SMALL GRAVEL		
	254		259	BROWN SANDY CLAY		
30	259	11	270	BROWN SANDY CLAY & SAND FINE TO MED. & SMALL GRAVEL		
65	270	12	282	SAND FINE TO MED. COARSE SMALL TO MED. GRAVEL		
30	282		300	BROWN SAND CLAY & SAND FINE TO MED. COARSE SMALL TO LARGE GRAVEL		
50	300	27	327	SAND FINE TO MED. COARSE SMALL GRAVEL LIMEROCK LEDGES & FEW CLAY STKS.		
70	327	14	341	SAND FINE TO MED. COARSE SMALL TO MED. GRAVEL		
	341		346	BROWN SANDY CLAY & SAND STKS.		
45	346	09	355	SAND FINE TO MED. COARSE & FEW CLAY STKS.		
	355		380	BROWN SANDY CLAY, LIMEROCK, & FEW FINE SAND STKS.		
35	380	13	393	SAND FINE SMALL FEW CLAY STKS.		
	393		423	BROWN CLAY & FEW ROCK LEDGES		
good	423	27	450	SANDSTONE, BROWN ROCK USED LOTS OF WATER		
good	450	10	460	BROWN ROCK SANDSTONE SOAPSTONE		
	460		480	GRAY & BLUE SHALE		

HENKLE DRILLING & SUPPLY CO., INC.

GARDEN CITY, KANSAS

Phone 276-3278

TEST HOLES

DOMESTIC WELLS

STOCK W-75

IRRIGATION & INDUSTRIAL WELLS

SUBLETTE, KANSAS

Phone 675-4311