

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 047 KEARNY | NC SW 1/4 | 11 | T 26 S | R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM DEERFIELD; APPX 11 3/4 MILES SOUTH

2 WATER WELL OWNER: RIDGEVIEW FARMS
 RR#, St. Address, Box # : PO BOX 595 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : GARDEN CITY, KS 67846-0595 Application Number: 33599

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 491 | ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 312 ft. below land surface measured on mo/day/yr 07/27/06
 Pump test data: Well water was 405 ft. after 4 hours pumping 450 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 491 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 491 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 346 ft. to 486 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 491 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHEAST How many feet? 73

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	47	07 FINE SAND			
47	55	01 CLAY			
55	85	05 SAND 11 GRAVEL			
85	89	04 SANDY CLAY			
89	164	05 SAND 13 FINE GRAVEL 01 CLAY			
164	169	04 SANDY CLAY			
169	179	05 SAND 13 FINE GRAVEL			
179	188	04 SANDY CLAY			
188	205	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/21/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/09/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 047 KEARNY | 1/4 NC 1/4 SW 1/4 | 11 | T 26 S | R 35 W

2 WATER WELL OWNER: RIDGEVIEW FARMS
RR#, St. Address, Box # : PO BOX 595 Board of Agriculture, Division of Water Resources
City, State, ZIP code : GARDEN CITY, KS 67846-0595 Application Number: 33599

FROM	TO	LITHOLOGIC LOG
205	221	05 SAND 01 CLAY
221	250	04 SANDY CLAY 05 SAND
250	266	05 SAND 13 FINE GRAVEL
266	297	04 SANDY CLAY 05 SAND
297	320	05 SAND
320	347	04 SANDY CLAY 05 SAND
347	362	07 FINE SAND 08 MEDIUM SAND
362	367	01 CLAY
367	370	07 FINE SAND 08 MEDIUM SAND
370	402	04 SANDY CLAY 05 SAND
402	409	07 FINE SAND
409	411	05 SAND 28 ROCK
411	429	06 VERY FN SAND
429	470	23 SANDSTONE
470	486	23 SANDSTONE
486	533	01 CLAY
533	550	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/21/06 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/09/06
under the business name of HENKLE DRILLING & SUPPLY by (signature) Bruce J. Reichman