

26-35-22add Sample _____ log of test hole _____ augered drilled
 (Well No.)
 by C. K. Minter for Kansas Geological Survey
ADD
 in SE SE NE sec. 22, T. 26 S, R. 35 W; about 2.6 miles north of the county line
 (Location)
and about 25 feet west of the center of road
12-12-67; depth to water, _____ feet;
 (Date)
 altitude of land surface 2983 feet.

	Thickness, feet	Depth, feet
Dune sand, fine to medium, some coarse	20	20
Sand, fine to very coarse and fine gravel	18	38
Sand, fine to very coarse and fine to medium gravel, some coarse; contains tan clay streaks	32	70
Clay, gray to tan, sandy	8	78
Sand, fine to very coarse and fine gravel; contains very thin tan to gray limy clay streaks	18	96
Clay, limy, tan to gray	5	101
Sand, very fine to medium; contains tan silt, (acts like Dune Sand); and thin tan limy clay streaks	43	144
Clay, silty, dark gray	14	158
Clay, dark gray to blue; interbedded with fine to medium sand and fine to medium gravel layers	24	182
Clay, very sandy, silty, reddish tan	35	217
Sand, fine to very coarse and fine to medium gravel; contains streaks of reddish-tan silty sandy clay and tan limy clay	23	240
Clay, very sandy silty reddish-tan; contains streaks of medium to very coarse sand and fine to medium gravel	10	250
Sand, medium to very coarse and fine to medium gravel, some coarse; contains tan reddish-tan sandy clay and yellow tan limy sandy clay	58	308

