

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY SW 1/4 SE 1/4 SE 1/4 09 T 26 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 9.0 MILES SOUTH OF LAKIN.

2 WATER WELL OWNER: KOEHN, WILLIAM  
 RR#, St. Address, Box #: 5890 E. ROAD THREE Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: ULYSSES, KS 67880- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 290 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 125 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 125 ft. below land surface measured on mo/day/yr 08/17/92  
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 10. in. to 290 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 290 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 170 ft. to 210 ft., From 270 ft. to 290 ft.  
 From 230 ft. to 250 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 290 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	07 FINE SAND			
10	135	30 ROCK & CLAY 05 SAND 11 GRAVEL			
135	137	01 CLAY			
137	141	01 CLAY			
141	150	01 CLAY 05 SAND			
150	175	05 SAND			
175	183	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
183	199	04 SANDY CLAY 05 SAND			
199	217	01 CLAY			
217	249	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/18/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/16/92 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
COUNTY: 047 KEARNY | SW 1/4 SE 1/4 SE 1/4 | 09 | T 26 S | R 36 W

2 WATER WELL OWNER: KOEHN, WILLIAM  
RR#, St. Address, Box #: 5890 E. ROAD THREE Board of Agriculture, Division of Water Resources  
City, State, ZIP code: ULYSSES, KS 67880- Application Number:

FROM	TO	LITHOLOGIC LOG
249	285	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
285	290	05 SAND
290	298	01 CLAY
298	301	05 SAND
301	320	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/18/92 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/16/92  
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichardt*