


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Kearny County	Fraction 1/4 1/4 SW 1/4	Section number 22	Township number T 26 S	Range number R 36 E/W
2. Distance and direction from nearest town or city: 12 South of Lakin 6 1/2 East, 1/2 North Street address of well location if in city:			3. Owner of well: Earl Berlier R.R. or street: Lakin, KS 67860 City, state, zip code:		
4. Locate with "X" in section below: Sketch map: 			6. Bore hole dia. 26 in. Completion date 7-15-79 Well depth 360 ft.		
5. Type and color of material			7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
			8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
			9. Casing: Material Steel Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 1 ft. in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 36.87 lbs./ft. Dia. 16 in. to 360 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. .219		
			10. Screen: Manufacturer's name Johnson Type Johnson Galv. Dia. 100-16" Slot/gauze <input type="checkbox"/> Length <input type="checkbox"/> Set between <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? yes Size range of material 1/4 to 5/8		
			11. Static water level: <input type="checkbox"/> mo./day/yr. 150 ft. below land surface Date 5-7-79		
(Use a second sheet if needed)			12. Pumping level below land surfaces: 155 ft. after 2 hrs. pumping 1200 g.p.m. 157 ft. after 4 hrs. pumping 1500 g.p.m. Estimated maximum yield 1500 g.p.m.		
			13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
			14. Well head completion: <input type="checkbox"/> Pitless adapter 1 ft. inches above grade		
			15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		
			16. Nearest source of possible contamination: ft. <input type="checkbox"/> Direction N/A Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
(Use a second sheet if needed)			17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Could 5 stg. 12" Bowf Model number <input type="checkbox"/> HP 125 Volts <input type="checkbox"/> Length of drop pipe 240 ft. capacity 1000 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter Wilson Drilling Co. 208 Business name License No. <input type="checkbox"/> Address Box A, Garden City, KS 67844 Signed Shene Delaney Date 8/17/79 Authorized representative		
			18. Elevation:		
			19. Remarks:		
			Topography: <input checked="" type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

The Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

April 11, 1979

Earl Berlier
Kearny County

Location: SW $\frac{1}{4}$ 22-26-36 Pivot
Static Water Level
Test #1

0	50	Sand
50	76	Brown Clay
76	171	Med. to coarse gravel (loose)
171	180	Brown Clay 35% Gravel
180	198	Med. to coarse gravel 10% Clay (loose)
198	215	Brown Clay
215	237	Fine to med. sand and gravel streaks of coarse gravel (loose)
237	253	Brown Clay
253	290	Fine to med. sand and gravel (loose)
290	348	Fine to med. sand and gravel streaks of coarse gravel (loose)
348	360	Brown Sandy Clay streaks of gravel 35% (loose)
360	373	Brown & Gray Clay with Brown Rock (tight) (hard streaks)
373	381	Gray & Yellow Clay with Brown Rock (hard)
381	386	Yellow Clay & Shale (hard)