


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Kearny	Fraction SW 1/4 NW 1/4 NE 1/4	Section number 36	Township number T 26 S R 36 E W	Range number
2. Distance and direction from nearest town or city: South of Lakin on Hiway 25 to the Grant-Kearny line, Street address of well location if in city: 3 3/4 E., 3/4 N.				3. Owner of well: McCormick Ranch R.R. or street: Box 231 City, state, zip code: Lakin, Kansas 67860		
4. Locate with "X" in section below: 				Sketch map:		
5. Type and color of material				From	To	6. Bore hole dia. 26 in. Completion date 1-31-77 Well depth 400 ft.
						7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
						8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
						9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 36.87 lbs./ft. Dia. 16 in. to 401 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gauge No. 250-29 msc
						10. Screen: Manufacturer's name Johnson Type galv. Dia. 16" Slot 1/8" Length 20 ft. Set between 160-180 ft. and 330-370 ft. Perforated 180-330 ft. and 370-400 ft. Gravel pack? yes Size range of material 3/4" down
						11. Static water level: 146 ft. below land surface Date 1-10-77 mo./day/yr.
						12. Pumping level below land surfaces: 220 ft. after 6 hrs. pumping 100 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1200 g.p.m.
						13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.
						14. Well head completion: ☐ Pitless adapter 12 inches above grade
						15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: N/A ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No
						17. Pump: Not installed Manufacturer's name Poertgen (used) Model number 126B HP 150 Volts Length of drop pipe 300 ft. capacity 1200 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
						(Use a second sheet if needed)
18. Elevation:		19. Remarks: Customer installed his pump -		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter-Wilson Drilling Co. 208 Business name Box A Garden City, Ks. License No. ☐ Address Box A Garden City, Ks. Signed [Signature] Date 2-30-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

TEST HOLE LOG

Wagner's

Box 10, Ulysses, Kansas 67880

Water Wells & Test Holes

Phone (316) 356-2396

Date 12-15-1976Test No. 6Qtr. NE Sec. 36Twp. 26 Rge. 36Co. KearnyLand Owner McCormick FarmsAddress Lakin, Kansas

CONSOLIDATED-SALINA

last quarter line in center

FOOTAGE	Description of Strata
0 - 20	Surface and fine sand
20 - 60	Fine sand
60 - 80	Brown clay
80 - 100	Fine sand
100 - 180	Coarse sand and brown clay last 10 ft.
180 - 220	Blue clay
220 - 240	Coarse sand and some blue clay 60%
240 - 260	" " " " & embedded brown clay ✓
260 - 280	Coarse sand & brown clay 50%
280 - 320	Blue clay
320 - 340	Brown clay: Br. sandy clay 330-340 50%
340 - 380	Loose coarse sand: Brown clay 368-380
380 - 400	Br. clay and fine sand 30%
400 - 420	Brown clay
420 - 440	" " & some blue shale
	Hole at 440 ft.

0 - 160 plain
~~140 - 160~~ per
 160 - 180 screen
 180 - 330 per
 330 - 370 screen
 370 - 440 - per
 60' screen