

17878

KSA 82a-1212

*The
Professionals*

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269

• P.O. Box A

• GARDEN CITY, KANSAS 67846

Lakin Dairy
Kearny County
11-23-07

Location: NE $\frac{1}{4}$ 5-26-36 - South on Lakin Lane to the correction line -
1-3/4 miles south, 1 mile west, 1 $\frac{1}{4}$ miles north,
 $\frac{1}{4}$ mile west & $\frac{1}{4}$ mile south
- Just west of pivot

Static Water Level - 170 ft.

Test #1

0'	to	20'	-	Fine sand
20'	to	24'	-	Brown clay
24'	to	61'	-	Medium to coarse sand & small gravel
61'	to	64'	-	Brown sandy clay
64'	to	157'	-	Fine to coarse sand & gravel & a little clay
157'	to	164'	-	Cemented sand - hard
164'	to	197'	-	Sandy clay & sand streaks
197'	to	220'	-	Gray clay
220'	to	242'	-	Medium to coarse sand
242'	to	257'	-	Brown sandy clay
257'	to	270'	-	Fine to medium sand & a little clay
270'	to	341'	-	Brown & white sandy clay & a little caliche
341'	to	361'	-	Medium sand & some clay streaks
361'	to	377'	-	Medium to coarse sand - clean
377'	to	394'	-	Brown & yellow clay
394'	to	410'	-	Shale