

26-36-32 CCC sample _____ log of test hole _____ augered (drilled)
 (Well No.)
 by C.K. Minter Drilling Co for Kansas Geological Survey
 in S.W.S.W. Sec 32, T26S, R36W; about
 (Location)
 600 ft east and 30 ft north of S.W. corner
 Jan 4, 1968; depth to water, _____ feet;
 (Date)
 altitude of land surface 3088 _____ feet.

(2109)

	Thickness, feet	Depth, feet
Silt, very sandy, brown	2	2
Sand, very fine to fine; contain brown sandy loam	6	8
Sand, very fine to medium, silty; contains tan-white caliche streaks	7	15
Sand fine to medium; contains tan silt	6	21
Sand, very fine to coarse; contains tan-white caliche streaks	31	52
Sand, very fine to coarse, with silty; contains tan-white caliche streaks	25	77
Sand, fine to very coarse and fine to medium gravel; contains ^{this band} fine cemented streaks	21	98
Sand, fine to very coarse and fine to medium gravel; drilled loose; contains thin band tan-white caliche streaks at 101 and 108 feet.	17	115
Silt, tan soft sandy; contains tan-white fine cemented sand and gravel streaks	16	131
Sand, fine to coarse and fine gravel; cemented by caliche; contains tan silty clay streaks	26	157
Clay, tan silty	5	162

-6-36-32ccc Sample _____ log of test hole _____ augered drilled
(Well No.)

in _____
(Location)

_____; depth to water, _____ feet;
(Date)

altitude of land surface _____ feet.

	Thickness, feet	Depth, feet
Silt, very sandy tan	6	168
Clay, tan, silty; contains ^{very fine to coarse} sand and fine gravel; drills tight	19	187
Clay, blue; interbedded with fine to very coarse sand and ^{fine} gravel streaks	21	208
Clay, blue and tan; contains thin fine to very coarse sand streaks	39	247
Sand, very fine to coarse and fine gravel; contains blue and tan clay streaks	13	260
Sand, fine to coarse and fine gravel; contains ^{fine} cemented layers (bit chatter)	40	300
Sand, fine to coarse and fine to medium gravel (chilled hard)	8	308
Clay, light tan clay, hard to work	3	311
Silt, tan to pink to yellow	11	322
Sand, fine to coarse and fine to medium gravel (rounded) contains tan white caliche streaks	23	345
Clay, sandy, tan	3	348

Sand, fine to coarse and fine to medium gravel, 31 379
~~clay~~ 50% of gravel sandstone phenocrasts 22 401
 Shale, gray black; contains hard streaks of very fine grained sandstone
 with ~~streaks of~~ ~~soft~~ ~~light gray~~ ~~caliche~~