

The Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 . P.O. Box A . GARDEN CITY, KANSAS 67846

EARL BERLIER
Kearny County
May 18, 1982

Location: Well #2 South of Lakin between mile markers 66 & 65, 1 $\frac{1}{4}$ Southwest

Static Water Level -

Test #

0	20	Sand
20	95	Medium Sand & Gravel Some Coarse Gravel
95	112	Fine to Medium Sand & Gravel Some Coarse Gravel 30% Clay
112	181	Fine to Medium Sand & Gravel Some Coarse Gravel 10% Clay
181	193	Brown Clay
193	283	Fine to Medium Sand & Gravel Some Coarse Gravel
283	290	Brown Clay

Drilled 10 5/8 Hole 290'
Set 6 5/8 Pipe 288'
30' Perf