


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Kearny</b>	Fraction <b>NE 1/4 NE 1/4 NE 1/4</b>	Section number <b>21</b>	Township number <b>T 26</b>	Range number <b>S 37 R 37</b>
2. Distance and direction from nearest town or city: <b>from the four way stop at Ulysses 14 miles north</b>				3. Owner of well: <b>H. G. Webber</b> R.R. or street: <b>114 South Main</b> City, state, zip code: <b>Ulysses, KS. 67880</b>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>27</b> in. Completion date <b>6-14-78</b> Well depth <b>389</b> ft.		
				7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From		To		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Surface		0		2		9. Casing: Material <b>steel</b> Height Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <b>16</b> <b>BVC</b> Weight <b>36.8</b> lbs./ft. Dia. <b>16</b> in. to <b>236</b> ft. depth Wall Thickness: inches or Dia. <b>16</b> in. to <b>389</b> ft. depth gage No. <b>.219</b>
Very fine sand w/clay breakers		2		20		10. Screen: Manufacturer's name <b>Lakewood Pipe of Texas</b> Type <b>316 steel</b> Dia. <b>16"</b> Slot/gauze <b>3/16"</b> Length <b>103</b> Set between <b>286</b> ft. and <b>389</b> ft. ft. and <b>1</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1 x 5/8"</b>
Brown and blue clay w/very fine sand strips		20		163		11. Static water level: <b>87</b> ft. below land surface Date <b>6/1/78</b>
Very fine to fine sand w/embedded strips		163		188		12. Pumping level below land surfaces: <b>147</b> ft. after <b>9.8</b> hrs. pumping <b>1705</b> g.p.m. ft. after <b>   </b> hrs. pumping <b>   </b> g.p.m. Estimated maximum yield <b>2000</b> g.p.m.
Sandy clay w/fine sand strips		188		210		13. Water sample submitted: <b>   </b> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <b>   </b>
Brown sandy clay w/fine sand strips		210		233		14. Well head completion: <b>24</b> inches above grade <input type="checkbox"/> Pitless adapter
Medium to coarse sand and gravel w/clay breakers		233		292		15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
Yellow chalk, brown clay and sandrock 10%		292		308		16. Nearest source of possible contamination: <b>field</b> ft. Direction <b>   </b> Type <b>field</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Sandrock, Cheyenne & Dakota, clay 60%		308		343		17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <b>   </b> Model number <b>   </b> HP <b>   </b> Volts <b>   </b> Length of drop pipe <b>   </b> ft. capacity <b>   </b> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Sandrock, Cheyenne & Dakota & clay 80%		343		389		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Houck Bros. Drlg. Co. 164</b> Business name License No. Address <b>Box 487, Ulysses, KS.</b> Signed <b>M. Beard</b> Date <b>6-20-78</b> Authorized representative
18. Elevation:		19. Remarks: <b>50 feet of Johnson Screen set between 236 and 286 feet</b>				
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5