

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
 COUNTY: 038 HAMILTON | SW 1/4 SE 1/4 SW 1/4 | 24 | T 26 S | R 41 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX 14 1/2 MILES SOUTH OF SYRACUSE

2 WATER WELL OWNER: JOHN LEWIS  
 RR#, St. Address, Box #: P. O. BOX 506 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: GARDEN CITY, KS 67855- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 462 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 260 ft. below land surface measured on mo/day/yr 03/20/93  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 9.875 in. to 462 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 462 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 362 ft. to 462 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 462 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? NORTH How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	03 SILTY CLAY			
2	19	04 SANDY CLAY			
19	32	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
32	45	20 LIMESTONE 23 SANDSTONE			
45	70	19 SHALE			
70	127	23 SANDSTONE 20 LIMESTONE			
127	230	21 SHALE & LMST			
230	265	16 V CRS GRAVEL 23 SANDSTONE 20 LIMESTONE			
265	318	23 SANDSTONE 20 LIMESTONE			
318	330	23 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/20/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/25/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:      : Fraction      : Section Number      : Township Number      : Range Number  
COUNTY: 038 HAMILTON      : SW    1/4 SE    1/4 SW    1/4      : 24      : T 26      S      : R 41    W

2 WATER WELL OWNER:      JOHN LEWIS  
RR#, St. Address, Box # : P. O. BOX 506      Board of Agriculture, Division of Water Resources  
City, State, ZIP code : GARDEN CITY, KS    67855-      Application Number:

FROM	TO	LITHOLOGIC LOG
330	342	23 SANDSTONE 20 LIMESTONE
342	430	23 SANDSTONE
430	438	20 LIMESTONE 23 SANDSTONE
438	462	23 SANDSTONE 20 LIMESTONE
462	475	20 LIMESTONE
475	482	28 ROCK

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/20/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145      This Water Well Record was completed on (mo/day/yr) 03/25/93 under the business name of HENKLE DRILLING & SUPPLY      by (signature) *Bruce J. Reichmuth*