

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 030 HAMILTON SW 1/4 SW 1/4 SW 1/4 36 T 26 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 16.0 MILES SOUTH OF SYRACUSE.

2 WATER WELL OWNER: LEWIS, JOHN  
 RR#, St. Address, Box #: SOUTH ROUTE, BOX 54 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: SYRACUSE, KS 67878- Application Number: 9,194

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 551 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 159 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 159 ft. below land surface measured on mo/day/yr 07/10/92  
 Pump test data: Well water was 464 ft. after 4 hours pumping 919 gpm

Estimated Yield 900 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 551 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 551 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 141 ft. to 551 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 551 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? SOUTH How many feet? 290

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	24	04 SANDY CLAY			
24	47	05 SAND 01 CLAY			
47	60	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND			
60	71	05 SAND 01 CLAY 13 FINE GRAVEL			
71	79	05 SAND 13 FINE GRAVEL			
79	100	04 SANDY CLAY 05 SAND			
100	106	05 SAND			
106	130	04 SANDY CLAY 05 SAND			
130	135	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/00/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/14/92 under the business name of HENKLE DRILLING & SUPPLY by (signature)

