

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HAMILTON NW 1/4 NW 1/4 NW 1/4 20 T 26 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SYRACUSE - S ON HIGHWAY 27, 13 M TO RD 34, W 5 MILES

2 WATER WELL OWNER: BRADDOCK, DAN
 RR#, St. Address, Box #: HC 01 -- BOX 50
 City, State, ZIP code : SYRACUSE, KS 67878- Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

4 DEPTH OF COMPLETED WELL 535 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 101 ft. below land surface measured on mo/day/yr 08/14/04
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 535 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 535 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 430 ft. to 530 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 160 ft., From 0 ft. to 0 ft.
 From 170 ft. to 535 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 160 ft. to 170 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY			
20	40	32 TAN CLAY 16 GRAY CLAY			
40	60	10 FINE-MEDSAND 16 GRAY CLAY			
60	80	02 FINE SAND 16 GRAY CLAY			
80	130	16 GRAY CLAY 36 BLUE CLAY			
130	160	22MED-COAR SAND 32 TAN CLAY			
160	180	32 TAN CLAY 11 BROWN CLAY 08 ROCK LAYERS			
180	200	32 TAN CLAY 29 SANDSTONE 19 LAYERS			
200	240	16 GRAY CLAY			
240	280	16 GRAY CLAY 29 SANDSTONE 19 LAYERS			

RECEIVED
 OCT 27 2004
 BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/16/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/13/04 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Judith Creek*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: HAMILTON	NW 1/4 NW 1/4 NW 1/4	20	T 26 S	R 41 W

2 WATER WELL OWNER: BRADDOCK, DAN

RR#, St. Address, Box #: HC 01 -- BOX 50

Board of Agriculture, Division of Water Resources

City, State, ZIP code: SYRACUSE, KS 67878-

Application Number:

FROM	TO	LITHOLOGIC LOG
280	300	29 SANDSTONE
300	400	29 SANDSTONE 16 GRAY CLAY 19 LAYERS
400	540	29 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/16/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/13/04 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*