

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HAMILTON SE 1/4 NE 1/4 NE 1/4 2 T 26 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SYRACUSE ON HIGHWAY 27 - 10 MILES SOUTH

2 WATER WELL OWNER: HOOK, KATHLENE
 RR#, St. Address, Box #: PO BOX 849 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SYRACUSE, KS 67878- Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	NW	NE	X
2	SW	SE	

4 DEPTH OF COMPLETED WELL 505 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 254 ft. below land surface measured on mo/day/yr 09/17/07
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 505 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 505 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 420 ft. to 500 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 505 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	40	32 TAN CLAY 12 SANDROCK LAYER 10 FINE-MED SAND			
40	60	39 SAND ROCK 02 FINE SAND			
60	80	10 FINE-MED SAND 32 TAN CLAY			
80	100	32 TAN CLAY			
100	120	10 FINE-MED SAND 32 TAN CLAY 36 BLUE CLAY			
120	160	36 BLUE CLAY 31 SHALE			
160	180	32 TAN CLAY 16 GRAY CLAY 29 SANDSTONE			
180	200	BROWN 29 SANDSTONE			
200	280	16 GRAY CLAY 29 SANDSTONE 19 LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/18/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/12/07 under the business name of JOE'S WELL SERVICE, INC. by (signature) Judith Creek

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: HAMILTON	SE 1/4 NE 1/4 NE 1/4	2	T 26 S	R 41 W

2 WATER WELL OWNER: HOOK, KATHLENE

RR#, St. Address, Box #: PO BOX 849

City, State, ZIP code: SYRACUSE, KS 67878-

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
280	300	29 SANDSTONE
300	360	29 SANDSTONE 16 GRAY CLAY
360	510	29 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/18/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/12/07 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Creek*