





# Henkle

## DRILLING & SUPPLY CO., INC.

3795 W. JONES AVE.  
316/277-2389  
FAX/277-0224

P.O. Box 639  
GARDEN CITY, KANSAS 67846

CUSTOMER'S NAME Charles Holdren DATE 7/9/90  
 STREET ADDRESS 417 North Johnson TEST # 1 E. LOG Yes  
 CITY & STATE Syracuse, Ks. 67878 DRILLER Shelden  
 COUNTY Hamilton QUARTER NW SECTION 11 TOWNSHIP 26 RANGE 42  
 LOCATION 90' East of the old well.

%	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL:
	From	Pay	To		Proposed Well Depth:
	0		2	Top soil.	
	2		84	Brown sandy clay & some small sand streaks.	
	84		113	Sand fine to medium coarse. Small to some medium gravel.	
	113		141	Brown sandy clay.	
	141		146	Brown sandy clay w/some small sand streaks.	
	146		164	Blue clay.	
50	164	7	171	Sand fine to medium, few coarse.	
	171		186	Brown sticky clay.	
40	186	20	206	Brown sandy clay w/some small sand streaks @ 186' & 191'.	
40	206	3	209	Sand fine to medium coarse, some small gravel.	
	209		221	Brown clay.	
	221		230	Gray soapstone.	
	230		233	Sandstone	
	233		241	Soapstone	
30	241	29	270	Sandstone. Lost circulation. Mix mud.	
	270		284	Cemented sandstone.	
25	284	28	312	Sandstone	
	312		315	Soapstone	
20	315	15	330	Sandstone	
	330		344	Soapstone & sandstone	
20	344	42	386	Sandstone	
	386		390	Soapstone	
30	390	29	419	Sandstone	
20	419	27	446	Soapstone & sandstone	
	446		462	Shale w/some Iron pyrite streaks.	
				Set up East	
				Pit on South	
				Move big hole 5' North of test hole.	
				30 - G-Gel	
				21 - Plug It	
				4 - Bran	
				4 - Lime	
				1 - Perma plug	
				1 - Bag Hole plug	