



**DRILLERS TEST LOG**

**CUSTOMER'S NAME:** Dr. Warren Schwartz **DATE:** 10/20/89  
**STREET ADDRESS:** 2401 Scarborough Drive **TEST #** 1 **E. LOG** Yes  
**CITY & STATE:** Anchorage, Alaska 99504 **DRILLER** Shelden  
**COUNTY** Hamilton **QUARTER** SW **SECTION** 14 **TOWNSHIP** 26 **RANGE** 42

**LOCATION** 290' North of the old well.

**WELL LOCATION**

Z	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL: _____
	From	Pay	TO		Proposed Well Depth:
	0		2	Top soil.	
	2		24	Brown sandy clay.	
	24		47	Sand fine to medium coarse.	
	47		69	Brown sandy clay.	
	69		183	Brown clay & some small sandstreaks & limerock ledges.	
20	183	28	211	Sandstone & brown rock ledges. Used water.	
	211		213	Gray & purple clay.	
	213		225	Gray clay & streaks of tan rock.	
60	225	25	250	Sand fine to medium coarse & brown rock. Lost circulation. Mixed drilling fluid.	
10	250	57	307	Gray soapstone w/lots black sandstone streaks. Drilled rough.	
	307		310	Gray soapstone.	
20	310	14	324	White & tan sandstone.	
10	324	22	366	Gray soapstone & sandstone streaks.	
10	366	14	380	Weathered shale w/lots sandstone streaks.	
15	380	20	400	Sandstone & shale.	
10	400	20	420	Shale & some sandstone streaks.	
20	420	25	445	Hard sandstone & streaks of shale.	
10	445	13	458	Green soapstone & some small sandstone streaks & limestone ledges.	
	458		459	Iron pyrite.	
20	459	41	500	Sandstone & gray soapstone. Drill loose in places.	
10	500	24	524	Brown rock ledges & sandstone.	
20	524	40	564	Sandstone & some brown & tan rock ledges.	
	564		566	False red bed.	
20	566	37	603	Sandstone & gray soapstone streaks.	
25	603	76	679	Sandstone. Used water. Drilled loose.	
	679		702	Red bed.	
				Well depth = 682'	
				Set up Northeast	
				Pit on Southeast	
				Move Big Rig over 4'.	
				16 - 50# Bags O-Gel	
				3 - 10# Bags Lime	
				4 - 50# Bags Chips Plug	
				1 - 50# Bag Celleflake	
				1 - Set 4 3/4" Drag Blades	

GARDEN CITY, KS 67846  
 3795 West Jones Ave.

HENKLE DRILLING & SUPPLY CO., INC.

316-277-2389

IRRIGATION HEADQUARTERS

TEST HOLES \* \* \* \* \* IRRIGATION & INDUSTRIAL WELLS \* \* \* \* \* STOCK WELLS