

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: HAMILTON Fraction NW 1/4 NW 1/4 NE 1/4 Section Number 6 Township Number T 26 S Range Number R 42 W

Distance and direction from nearest town or city street address of well if located within city?  
FROM SYRACUSE - 10 S. ON HIGHWAY & 10 WEST ON ROAD 31

2 WATER WELL OWNER: BELTZ, CHARLES RR#, St. Address, Box #: MCO1 -- BOX 11 City, State, ZIP code : SYRACUSE, KS 67878- Board of Agriculture, Division of Water Resources Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

		X	
1	NW	NE	
W			E
1	SW	SE	

4 DEPTH OF COMPLETED WELL 204 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 120 ft. below land surface measured on mo/day/yr 09/12/97  
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 45 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 204 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
Blank casing diameter 6 in. to 204 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 200 ft., From 0 ft. to 0 ft.  
GRAVEL PACK INTERVALS: From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
From 40 ft. to 204 ft., From 0 ft. to 0 ft.  
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
Grout Intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: ABANDONED WELL  
Direction from well? EAST How many feet? 30

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY FINE SAND			
20	40	FINE - MED SAND			
40	60	FINE - MED SAND CLAY			
60	100	CLAY			
100	140	FINE - MED SAND			
140	160	FINE - MED SAND COARSE SAND			
160	180	MED-COARSE SAND			
180	200	MED-COARSE SAND CLAY			
200	220	CLAY BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/12/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/22/97 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Curt*