

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 038 HAMILTON SE 1/4 NW 1/4 SE 1/4 17 T 26 S R 42 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SYRACUSE; APPX 12 3/4 MILES SOUTH & 9 MILES WEST

2 WATER WELL OWNER: JUSTIN VYN Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: PO BOX 1227 Application Number: 23,043
 City, State, ZIP code: SYRACUSE, KS 67878-1227

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 425 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. 0 ft.

1	NW	NE					
M i l e	W	E	SE	X	SW	NW	NE

WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was 355 ft. after 4 hours pumping 665 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 425 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 425 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 240 ft. to 420 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 425 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	100	04 SANDY CLAY 05 SAND			
100	112	07 FINE SAND 08 MEDIUM SAND			
112	113	04 SANDY CLAY			
113	122	05 SAND			
122	138	04 SANDY CLAY 05 SAND			
138	146	05 SAND			
146	149	04 SANDY CLAY			
149	162	05 SAND 01 CLAY			
162	169	04 SANDY CLAY 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 05/03/06 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: COUNTY: 038 HAMILTON	Fraction SE 1/4 NW 1/4 SE 1/4	Section Number 17	Township Number T 26 S	Range Number R 42 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: JUSTIN VYN
 RR#, St. Address, Box #: PO BOX 1227 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SYRACUSE, KS 67878-1227 Application Number: 23,043

FROM	TO	LITHOLOGIC LOG
169	177	05 SAND
177	202	04 SANDY CLAY
202	247	23 SANDSTONE 31 CALICHE
247	261	31 CALICHE 23 SANDSTONE
261	420	23 SANDSTONE 31 CALICHE
420	433	19 SHALE
433	440	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/03/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Benny K. Henkle*