

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

47548

1 LOCATION OF WATER WELL: County: Reno		Fraction $\frac{1}{4}$ SW $\frac{1}{4}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$		Section Number 26		Township No. T 26 S		Range Number R 6 ☐ E ☒ W																																																																			
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 1-1/2 miles South & 3-1/2 miles East of Pretty Prairie				Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																							
2 WATER WELL OWNER: Carl Wewe RR#, Street Address, Box #: 5877 NE 140 Ave. City, State, ZIP Code : Pretty Prairie, KS 67570																																																																											
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W E S -----1 mile-----		<table border="1" style="width:100%; text-align: center; border-collapse: collapse;"> <tr><td colspan="2">NW</td><td colspan="2">NE</td></tr> <tr><td colspan="2">SW</td><td colspan="2">SE</td></tr> </table>								NW		NE		SW		SE																																																											
NW		NE																																																																									
SW		SE																																																																									
		4 DEPTH OF COMPLETED WELL 76 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL 24 ft. below land surface measured on mo/day/yr 3/24/11 Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD 1000 gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter 30 in. to 76 ft., and..... in. to..... ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No																																																																									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 36 ft., Diameter..... in. to..... ft., Diameter..... in. to..... ft. Casing height above land surface 12 in., Weight 16.15 lbs./ft., Wall thickness or gauge No. 500 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 36 ft. to 76 ft., From..... ft. to..... ft. From..... ft. to..... ft., From..... ft. to..... ft. GRAVEL PACK INTERVALS: From 25 ft. to 76 ft., From..... ft. to..... ft. From..... ft. to..... ft., From..... ft. to..... ft.																																																																											
6 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☐ Bentonite ☐ Other Grout Intervals: From 2 ft. to 25 ft., From..... ft. to..... ft., From..... ft. to..... ft. What is the nearest source of possible contamination: None within 1/4 mile ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well Distance from well																																																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0</td><td>3</td><td>Topsoil</td><td></td><td></td><td></td></tr> <tr><td>3</td><td>10</td><td>Clay, brown</td><td></td><td></td><td></td></tr> <tr><td>10</td><td>22</td><td>Sand, fine to medium</td><td></td><td></td><td></td></tr> <tr><td>22</td><td>24</td><td>Clay, tan</td><td></td><td></td><td></td></tr> <tr><td>24</td><td>74</td><td>Sand, fine to coarse</td><td></td><td></td><td></td></tr> <tr><td>74</td><td>76</td><td>Shale, red</td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	3	Topsoil				3	10	Clay, brown				10	22	Sand, fine to medium				22	24	Clay, tan				24	74	Sand, fine to coarse				74	76	Shale, red																											
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																						
0	3	Topsoil																																																																									
3	10	Clay, brown																																																																									
10	22	Sand, fine to medium																																																																									
22	24	Clay, tan																																																																									
24	74	Sand, fine to coarse																																																																									
74	76	Shale, red																																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 3/24/11 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/year) 4/4/11 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i>																																																																											
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																											