

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Reno		Center $\frac{1}{4}$ NW $\frac{1}{4}$	17	T 26 S	R 6 W
Distance and direction from nearest town or city street address of well if located within city? 3/4 mile Northeast of Pretty Prairie					
2 WATER WELL OWNER: Gilbert Stucky					
RR#, St. Address, Box #: R.R.			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code: Pretty Prairie, KS 67570			Application Number: 41,163		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 92 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1.15 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 15 ft. below land surface measured on mo/day/yr 7-1-94			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 80.0 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 1.6 in. to 92 ft., and in. to ft.			
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well					
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)					
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well					
Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted					
Water Well Disinfected? Yes X No					
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded
2 PVC		4 ABS	7 Fiberglass		Threaded
Blank casing diameter 16 in. to 51 ft., Dia		in. to ft., Dia		in. to ft.	
Casing height above land surface 12 in., weight 16.15 lbs./ft.		Wall thickness or gauge No. 500			
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		3 Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes	
			7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 51 ft. to 91 ft., From ft. to ft.					
From ft. to ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 20 ft. to 91 ft., From ft. to ft.					
From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination: No Contamination within 3/8 mile					
1 Septic tank		4 Lateral lines	7 Pit privy	10 Fuel storage	14 Abandoned water well
2 Sewer lines		5 Cess pool	8 Sewage lagoon	12 Fertilizer storage	15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	13 Insecticide storage	16 Other (specify below)
Direction from well? How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Loam Top Soil			
3	9	Clay Brown			
9	32	Sand-Medium			
32	58	Sand-Fine			
58	64	Clay-Brown			
64	91	Sand-Medium			
91	92	Shale-Red			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-1-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/yr) 7-18-94 under the business name of Peterson Irrigation Inc. by (signature) <i>Mike Peterson</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					