

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Reno		SW 1/4 SW 1/4 SE 1/4	35	T 26 S	R 6W EW
Distance and direction from nearest town or city street address of well if located within city? 10 east, 5 North 1/4 West of Kingman, Kansas					
2 WATER WELL OWNER: Donald Bergkamp JR.		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: RT# 2		Application Number:			
City, State, ZIP Code: PrettyPraire, Kansas 67570					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 76' ft. ELEVATION: NA			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 37' ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was NA ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter: 8 1/4" in. to 76' ft., and in. to ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		XX 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No... xx ...; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes x No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued xx Clamped			
1 Steel 3 RMP (SR)		Welded			
2 PVC 4 ABS		Threaded			
Blank casing diameter 5" in. to 61' ft., Dia. in. to ft., Dia. in. to ft.					
Casing height above land surface 15" in., weight Sdr. 26 or 160 lbs./ft. Wall thickness or gauge No. 160					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC xx 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped xxxx 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 66' ft. to 76' ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 76' ft. to 22' ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement xx 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 22' ft. to 6' ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank xx 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? south east		How many feet? App: 350'			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0'	13'	Heavy top soil.			
13'	27'	white clay.			
27'	33'	Soft white sandy clay.			
33'	38'	Brown clay.			
38'	51'	Medium Fine Sand.			
51'	65'	Course Sand & Fine Gravel.			
65'	76'	Course Sand & Fine Gravel.			
		Red Bed.			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) April 27-1988 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 112 This Water Well Record was completed on (mo/day/yr) Aug. 1-1988 under the business name of Wells Drilling Co. by (signature) <i>Sal Wells</i>					