

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: <u>Reno</u>	NW 1/4 NE 1/4 SE 1/4	13	T 26 S	R 7

Distance and direction from nearest town or city street address of well if located within city?

2 North, 1 Mile East & 1/2 North of Pretty Prairie

2 WATER WELL OWNER: <u>Pretty Prairie Golf Course</u>	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: <u>c/o Leon Pretty Prairie State Bank</u>	Application Number:
City, State, ZIP Code: <u>104 W. Main, Pretty Prairie, KS 67570</u>	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL <u>55</u> ft. ELEVATION:
	Depth(s) Groundwater Encountered <u>1</u> <u>10</u> ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL <u>10</u> ft. below land surface measured on mo/day/yr <u>9-11-95</u>
	Pump test data: Well water was ft. after hours pumping gpm
	Est. Yield <u>30-50</u> gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter <u>10</u> in. to <u>62</u> ft., and in. to ft.
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> ; If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes <u>X</u> No	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued <u>X</u> Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter <u>6</u> in. to <u>45</u> ft. Dia			Threaded
Casing height above land surface <u>12</u> in., weight <u>3.36</u> lbs./ft. Wall thickness or gauge No. <u>.255</u>			
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
SCREEN-PERFORATED INTERVALS: From <u>45</u> ft. to <u>55</u> ft. From ft. to ft.			
GRAVEL PACK INTERVALS: From <u>25</u> ft. to <u>55</u> ft. From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From <u>5</u> ft. to <u>25</u> ft. From ft. to ft.				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? <u>East</u> How many feet? <u>150 ft</u>				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	Top Soil			
1	8	Fine Sand			
8	16	Fine Sand with Small Clay Layers			
16	62	Fine to Medium Sand			
62		Red Shale			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>9-11-95</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>138</u> This Water Well Record was completed on (mo/day/yr) <u>9-18-95</u> under the business name of <u>Peterson Irrigation Inc.</u> by (signature) <u>Mike Petersen</u>
