

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Reno</u>	Fraction <u>NW 1/4 SE 1/4 SE 1/4</u>	Section number <u>1</u>	Township number <u>T 26 S</u>	Range number <u>R 7 E</u>
2. Distance and direction from nearest town or city: <u>2 N of</u>			3. Owner of well: <u>Larry Siebert</u>			
Street address of well location if in city: <u>Pretty Prairie, Ks.</u>			R.R. or street: <u>R2</u> City, state, zip code: <u>Pretty Prairie, Ks. 67570</u>			
4. Locate with "X" in section below:			Sketch map:			
			6. Bore hole dia. <u>10</u> in. Completion date <u>5-5-76</u> Well depth <u>50</u> ft.			
			7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
			8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
			9. Casing: Material <u>Plst</u> Height <u>Above</u> or below Threaded ☐ Welded ☐ Surface <u>16</u> in. RMP ☒ PVC ☐ Weight <u>1.95</u> lbs./ft. Dia. <u>6</u> in. to <u>50</u> ft. depth Wall Thickness: inches or Dia. <u>6</u> in. to <u>50</u> ft. depth gage No. <u>300</u>			
5. Type and color of material			From	To	10. Screen: Manufacturer's name <u>J+L</u>	
<u>Topsoil - sandy reddish</u>			<u>0</u>	<u>6</u>	Type <u>RMP</u> Dia. <u>6"</u>	
<u>Sand + Gravel yellow</u>			<u>6</u>	<u>28</u>	Slot/gauze <u>3/36"</u> Length <u>10'</u>	
<u>Sand + Gravel light yellow gray</u>			<u>28</u>	<u>50</u>	Set between <u>40</u> ft. and <u>50</u> ft.	
<u>clay gray</u>			<u>50</u>	<u>51</u>	Gravel pack? <u>yes</u> Size range of material <u>F-1/2"</u>	
					11. Static water level: <u>28</u> ft. below land surface Date <u>5-5-76</u>	
					12. Pumping level below land surfaces: <u>29</u> ft. after <u>1</u> hrs. pumping <u>20</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>50</u> g.p.m.	
					13. Water sample submitted: <u> </u> mo./day/yr. ☐ Yes ☒ No Date <u> </u>	
					14. Well head completion: ☐ Pitless adapter <u>16</u> inches above grade	
					15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
					16. Nearest source of possible contamination: ft. <u>100</u> Direction <u>SW</u> Type <u>septic</u> Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
			(Use a second sheet if needed)			
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: ☐ Hill ☒ Slope ☒ Upland ☐ Valley				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Miller Water Well Serv 137</u> Business name <u>Hutchinson, Ks</u> License No. <u> </u> Address <u> </u> Signed <u>Joe Miller</u> Date <u>6-16-76</u> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5