

1 LOCATION OF WATER WELL: County: <u>Reno</u>		Fraction <u>NW</u> Center of Quarter <u>1/4</u>	Section Number <u>13</u>	Township Number <u>T 26</u>	Range Number <u>R 7</u>
Distance and direction from nearest town or city street address of well if located within city? <u>1 Mile West, 3/4 Mile North 1320' East of Pretty prairie, Kans.</u>					
2 WATER WELL OWNER: <u>W.W. Graber Cr Jean A. Graber</u>		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # : City, State, ZIP Code : <u>Pretty Prairie, Kansas 67570</u>		Application Number <u>15,824 & 18263</u>			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: <u>106'</u> ft. ELEVATION: <u>NA</u> ft.			
1 Mile W E S		Depth(s) Groundwater Encountered 1. <u>42'</u> ft. 2. <u>NA</u> ft. 3. <u>NA</u> ft.			
		WELL'S STATIC WATER LEVEL <u>42'</u> ft. below land surface measured on mo/day/yr <u>May 4 - 84</u>			
		Pump test data: Well water was <u>NA</u> ft. after <u>NA</u> hours pumping <u>NA</u> gpm			
		Est. Yield <u>1200</u> gpm: Well water was <u>NA</u> ft. after <u>NA</u> hours pumping <u>NA</u> gpm			
		Bore Hole Diameter: <u>28"</u> in. to <u>106'</u> ft., and <u>NA</u> in. to <u>NA</u> ft.			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: <u>Glued X</u> Clamped <u>NA</u>			
1 Steel		3 RMP (SR)		6 Asbestos-Cement	
2 PVC <u>XX</u>		4 ABS		7 Fiberglass	
Blank casing diameter <u>16"</u> in. to <u>66</u> ft., Dia <u>NA</u> in. to <u>NA</u> ft., Dia <u>NA</u> in. to <u>NA</u> ft.		8 Concrete tile			
Casing height above land surface <u>18"</u> in., weight <u>SCH. 40</u> lbs./ft. Wall thickness or gauge No. <u>500</u>		9 Other (specify below)			
TYPE OF SCREEN OR PERFORATION MATERIAL:		10 Asbestos-cement			
1 Steel		3 Stainless steel		8 RMP (SR)	
2 Brass		4 Galvanized steel		9 ABS	
SCREEN OR PERFORATION OPENINGS ARE:		11 Other (specify)			
1 Continuous slot		5 Fiberglass		12 None used (open hole)	
2 Louvered shutter		6 Concrete tile		8 Saw cut	
3 Mill slot <u>XX</u>		7 Torch cut		11 None (open hole)	
4 Key punched		10 Other (specify)		9 Drilled holes	
SCREEN-PERFORATED INTERVALS: From <u>66</u> ft. to <u>106</u> ft., From <u>NA</u> ft. to <u>NA</u> ft., From <u>NA</u> ft. to <u>NA</u> ft.		GRAVEL PACK INTERVALS: From <u>19'</u> ft. to <u>106'</u> ft., From <u>NA</u> ft. to <u>NA</u> ft., From <u>NA</u> ft. to <u>NA</u> ft.			
6 GROUT MATERIAL:		3 Bentonite <u>XX</u> 4 Other <u>NA</u>			
1 Neat cement		2 Cement grout			
Grout intervals: From <u>0</u> ft. to <u>17'</u> ft., From <u>NA</u> ft. to <u>NA</u> ft., From <u>NA</u> ft. to <u>NA</u> ft.		What is the nearest source of possible contamination:			
1 Septic tank		4 Lateral lines		7 Pit privy	
2 Sewer lines		5 Cess pool		8 Sewage lagoon	
3 Watertight sewer lines		6 Seepage pit		9 Feedyard	
Direction from well? <u>South East</u>		How many feet? <u>2500'</u>		10 Livestock pens <u>XX</u>	
FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG			
0 3'		Top soil			
3' 7'		Brown Clay			
7' 12'		Course sand & clay			
12' 23'		Brown Clay			
23' 31'		Brown sandy clay			
31' 42'		Clay			
42' 57'		Med. Course sand			
57' 61'		Blue clay			
61' 87'		Course Sand & Fine gravel.			
87' 94'		White Clay w/ lime (Rough)			
94' 106'		Course Sand & Fine Gravel (very clean)			
106'		RED BED			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>May 4 - 1984</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>112</u> This Water Well Record was completed on (mo/day/yr) <u>May 7 - 84</u> under the business name of <u>Wells Drilling Co.</u> by (signature) <u>Wal Wells</u>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					