

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: <u>Reno</u>		<u>SE 1/4 SE 1/4 SE 1/4</u>		<u>18</u>		<u>T 26 S</u>		<u>R 7 EW</u>	
Distance and direction from nearest town or city street address of well if located within city?									
<u>5 mi W of Pretty Prairie - 24005 S High Point Rd</u>									
2 WATER WELL OWNER:		<u>Margroff Kraus</u>							
RR#, St. Address, Box # :		<u>229 S Park</u>							
City, State, ZIP Code :		<u>Pretty Prairie, KS 67570</u>							
		Board of Agriculture, Division of Water Resources Application Number:							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>50</u> ft. ELEVATION:							
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL <u>26</u> ft. below land surface measured on mo/day/yr <u>6-11-92</u>							
		Pump test data: Well water was <u>4.7</u> ft. after <u>1</u> hours pumping <u>5</u> gpm							
		Est. Yield <u>5</u> gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter <u>9</u> in. to <u>53</u> ft., and in. to ft.							
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well							
		☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well							
		Was a chemical/bacteriological sample submitted to Department? Yes.....No <u>X</u> ; If yes, mo/day/yr sample was submitted							
		Water Well Disinfected? Yes <u>X</u> No							
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued <u>X</u> Clamped							
1 Steel 3 RMP (SR)		Welded							
☒ PVC 4 ABS		Threaded							
Blank casing diameter <u>6</u> in. to <u>40</u> ft., Dia		in. to ft., Dia							
Casing height above land surface <u>12</u> in., weight <u>3.37</u> lbs./ft. Wall thickness or gauge No. <u>160</u>									
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC 10 Asbestos-cement							
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)									
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:		☒ Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)							
SCREEN-PERFORATED INTERVALS: From <u>40</u> ft. to <u>50</u> ft., From ft. to ft.									
GRAVEL PACK INTERVALS: From <u>23</u> ft. to <u>53</u> ft., From ft. to ft.									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite 4 Other									
Grout Intervals: From <u>3</u> ft. to <u>23</u> ft., From ft. to ft., From ft. to ft.									
What is the nearest source of possible contamination:		10 Livestock pens ☒ 14 Abandoned water well 11 Fuel storage 15 Oil well/Gas well 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage 1 Septic tank 4 Lateral lines 7 Pit privy 2 Sewer lines 5 Cess pool 8 Sewage lagoon 3 Watertight sewer lines 6 Seepage pit 9 Feedyard							
Direction from well? <u>NW</u>		How many feet? <u>130</u>							
FROM	TO	LITHOLOGIC LOG		FROM	TO	PLUGGING INTERVALS			
<u>0</u>	<u>6</u>	<u>Br clay</u>							
<u>6</u>	<u>25</u>	<u>sand & Gravel</u>							
<u>25</u>	<u>41</u>	<u>Br clay - wt rock</u>							
<u>41</u>	<u>47</u>	<u>F Sand</u>							
<u>47</u>	<u>53</u>	<u>Shale</u>							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>6-11-92</u> and this record is true to the best of my knowledge and belief. Kansas									
Water Well Contractor's License No. <u>447</u> This Water Well Record was completed on (mo/day/yr) <u>6-13-92</u>									
under the business name of <u>Miller Drilling</u> by (signature) <u>E. Miller</u>									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									