

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.


48183- North well

1 LOCATION OF WATER WELL: County: Reno Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 7 3/4 South, 1/4 West of Arlington	Fraction 1/4 NW 1/4 SW 1/4 NE 1/4	Section Number 21	Township No. T 26 S	Range Number R 8 ☐ E ☒ W
---	--------------------------------------	----------------------	------------------------	--

Global Positioning System (GPS) information:

Latitude: (in decimal degrees)
 Longitude: (in decimal degrees)
 Elevation:
 Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27
 Collection Method:
☐ GPS unit (Make/Model:)
☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey
 Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m

2 WATER WELL OWNER: Damon Stauffer
 RR#, Street Address, Box #: 20918 West Prettv Prairie Road
 City, State, ZIP Code : Arlington, KS 67514

3 LOCATE WELL WITH AN "X" IN SECTION BOX:
 N
**4 DEPTH OF COMPLETED WELL** 65 ft.

Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft.
 WELL'S STATIC WATER LEVEL..... ft. below land surface measured on mo/day/yr. 12-7-12
 Pump test data: Well water was 50' ft. after 3 hours pumping 465 gpm
 EST. YIELD 470 gpm. Well water was 50' ft. after 3 1/2 hours pumping 470 gpm
 Bore Hole Diameter 40 in. to 65 ft., and in. to ft.
 WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well
☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below)
☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well
 Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No
 If yes, mo/day/yr sample was submitted.....
 Water well disinfected? ☒ Yes ☐ No

5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other
 CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded
 Casing diameter 16 in. to 65 ft., Diameter in. to ft., Diameter in. to ft.
 Casing height above land surface 18 in., Weight Sch 40 lbs./ft., Wall thickness or gauge No.

TYPE OF SCREEN OR PERFORATION MATERIAL:

☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole)
☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify)

SCREEN-PERFORATED INTERVALS: From 65 ft. to 45 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 65 ft. to 20 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other
 Grout Intervals: From ft. to ft., From 20 ft. to 0 ft., From ft. to ft.

What is the nearest source of possible contamination:

☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below)
☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well
☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well ☐ None

Direction from well Distance from well

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	4	Sandy top soil			
4	10	Sandy tan clay			
10	22	Sand & gravel- small			
22	25	Gray clay			
25	41	Sand & gravel- med, loose			
41	50	Sandy tan clay			
50	56	Fine sand			
56	65	Sand & gravel- small to med rock			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 4-18-13 and this record is true to the best of my knowledge and belief.
 Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/year) 4-26-13
 under the business name of Rosencrantz- Bemis by (signature) *Rosencrantz- Bemis*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>