

1 LOCATION OF WATER WELL: County: RENO		Fraction NE 1/4 NW 1/4 SE 1/4		Section Number 26	Township Number T 26 S	Range Number R 8W 8W
--	--	---	--	-----------------------------	----------------------------------	--------------------------------

Distance and direction from nearest town or city street address of well if located within city?
4 Miles west 7 Miles North 1/4 East 1/4 North 1/4 East Of Kingman, Kns.

2 WATER WELL OWNER: Lloyd Patterson RR#, St. Address, Box #: RT#1- Box 126 City, State, ZIP Code: Kingman, Kans. 67068		Board of Agriculture, Division of Water Resources Application Number:
---	--	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

N	
W	E
S	

4 DEPTH OF COMPLETED WELL: **36'** ft. ELEVATION: _____

Depth(s) Groundwater Encountered 1. **11'** ft. 2. _____ ft. 3. _____ ft.

WELL'S STATIC WATER LEVEL **10'** ft. below land surface measured on mo/day/yr **May 10-1991**

Pump test data: Well water was **NA** ft. after _____ hours pumping _____ gpm

Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm

Bore Hole Diameter: **7 7/8"** in. to **36'** ft., and _____ in. to _____ ft.

WELL WATER TO BE USED AS:

5 Public water supply	8 Air conditioning	11 Injection well
XX Domestic	3 Feedlot	6 Oil field water supply
2 Irrigation	4 Industrial	7 Lawn and garden only
		10 Monitoring well
		12 Other (Specify below)

Was a chemical/bacteriological sample submitted to Department? Yes _____ No **X** If yes, mo/day/yr sample was submitted _____

Water Well Disinfected? Yes **X** No _____

5 TYPE OF BLANK CASING USED:		3 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped _____
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded _____
XX 2 PVC	4 ABS	7 Fiberglass		Threaded _____
Blank casing diameter 5 in. to 26' ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.				
Casing height above land surface 14" in., weight 160 lbs./ft. Wall thickness or gauge No. SDR 26				
TYPE OF SCREEN OR PERFORATION MATERIAL:		XX PVC	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify) _____
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped	XX 8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes	
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify) _____	
SCREEN-PERFORATED INTERVALS: From 26' ft. to 36' ft., From _____ ft. to _____ ft.				
GRAVEL PACK INTERVALS: From _____ ft. to _____ ft., From _____ ft. to _____ ft.				
From 36' ft. to 19' ft., From _____ ft. to _____ ft.				

6 GROUT MATERIAL:		1 Neat cement	XX 2 Cement grout	3 Bentonite	4 Other _____
Grout Intervals: From 19' ft. to 0' ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:		10 Livestock pens	14 Abandoned water well		
XX 1 Septic tank	4 Lateral lines	7 Pit privy	11 Fuel storage	15 Oil well/Gas well	
2 Sewer lines	5 Cess pool	8 Sewage lagoon	12 Fertilizer storage	16 Other (specify below)	
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	13 Insecticide storage		
Direction from well? SE		How many feet? 110'			

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0'	4'	Top soil.			
4'	11'	Brown sand.			
11'	13'	Fine sand.			
13'	20'	Clay.			
20'	27'	Medium fine sand/			
27'	36'	Course sand.			
		Red Bed.			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) May 10 -91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 112 This Water Well Record was completed on (mo/day/yr) May 28 1991 under the business name of Wells Drilling Co. by (signature) <i>Sal Wells</i>	
--	--