


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Sedgwick	SW 1/4 NE 1/4 SE 1/4	26	T 27 S	R 1 E (W)

Distance and direction from nearest town or city street address of well if located within city?

1029 S. West Street, Wichita, Kansas

2 WATER WELL OWNER:	Batson Properties	Paragon NDT & Finishes, Inc.	01968021	MW-4D
RR#, St. Address, Box # :	1029 S. West Street	1015 S. West Street	Board of Agriculture, Division of Water Resources	
City, State, ZIP Code :	Wichita, KS 67213	Wichita, KS 67213	Application Number:	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL	67	ft.	ELEVATION:	Approx. 1299			
	Depth(s) Groundwater Encountered	1	14	ft.	2	ft.	3	ft.
	WELL'S STATIC WATER LEVEL	13.2	ft. below land surface measured on	mo/day/yr	11/11/96			
	Pump test data:	Well water was	ft. after	hours pumping	gpm			
	Est. Yield	N/A	gpm:	Well water was	ft. after	hours pumping	gpm	
	Bore Hole Diameter	8.25	in. to	67	ft., and	in. to	ft.	
WELL WATER TO BE USED AS:	5 Public water supply	8 Air conditioning	11 Injection well					
1 Domestic	3 Feedlot	6 Oil field water supply	9 Dewatering	12 Other (Specify below)				
2 Irrigation	4 Industrial	7 Lawn and garden only	(10) Monitoring well					
Was a chemical/bacteriological sample submitted to Department? Yes.....No..X.....; If yes, mo/day/yr sample was submitted								
Water Well Disinfected? Yes No X								

5 TYPE OF BLANK CASING USED:	3 Wrought iron	8 Concrete tile	CASING JOINTS: Glued	Clamped				
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded				
(2) PVC	4 ABS	7 Fiberglass		Threaded				
Blank casing diameter	2	in. to	67	ft., Dia	in. to	ft., Dia	in. to	ft.
Casing height above land surface	-2	in., weight	lbs./ft. Wall thickness or gauge No.	Sch 40				
TYPE OF SCREEN OR PERFORATION MATERIAL:	(7) PVC	10 Asbestos-cement						
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)				
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)				
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)					
1 Continuous slot	(3) Mill slot	6 Wire wrapped	9 Drilled holes					
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)					
SCREEN-PERFORATED INTERVALS:	From	56	ft. to	67	ft., From	ft. to	ft.	
	From	ft. to	ft., From	ft. to	ft.			
GRAVEL PACK INTERVALS:	From	53	ft. to	67	ft., From	ft. to	ft.	
	From	ft. to	ft., From	ft. to	ft.			

6 GROUT MATERIAL:	1 Neat cement	(2) Cement grout	(3) Bentonite	4 Other							
Grout Intervals:	From	0	ft. to	41	ft., From	41	ft. to	56	ft., From	ft. to	ft.
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well						
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well							
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)							
13 Insecticide storage											

Direction from well?

How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	0.5	Concrete Pavement & Crushed Limestone Subgrade			
0.5	5	Silty Lean Clay			
5	6	Sandy Lean Clay			
6	10	Clay, Fine Sand			
10	14	Fine to Medium Sand			
14	23.5	Fine to Coarse Sand, Trace Gravel			
23.5	64	Medium to Coarse Sand			
64	67	Fat Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10/16/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 11/18/96 under the business name of Terracon Consultants, Inc. by (signature) [Signature]
--