

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number																																																																								
County: Sedgwich		NE 1/4 SE 1/4 SE 1/4	5	T 27 S	R 1 E/W																																																																								
Distance and direction from nearest town or city street address of well if located within city? 2411 Callahan St. Wichita, Kans.																																																																													
2 WATER WELL OWNER: Chris Klaver																																																																													
RR#, St. Address, Box # : 2411 Callahan St. 67205			Board of Agriculture, Division of Water Resources																																																																										
City, State, ZIP Code : Wichita, Kansas 67205			Application Number:																																																																										
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 75' ft. ELEVATION:																																																																											
		Depth(s) Groundwater Encountered 1. 30' ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 27.5' ft. below land surface measured on mo/day/yr Sept. 13 1999. Pump test data: Well water was ft. after hours pumping gpm Est. Yield 35 gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 1/2" in. to 75' ft. and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial XX Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes.....No.....XX; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes XX No																																																																											
5 TYPE OF BLANK CASING USED:																																																																													
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued XX Clamped 2 PVC XX 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Threaded																																																																													
Blank casing diameter 5" in. to 65' ft. Dia in. to ft. Dia in. to ft. Casing height above land surface 14" in. weight 355 lbs./ft. Wall thickness or gauge No. 2.14																																																																													
TYPE OF SCREEN OR PERFORATION MATERIAL:																																																																													
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC XX 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 9 ABS 12 None used (open hole)																																																																													
SCREEN OR PERFORATION OPENINGS ARE:																																																																													
1 Continuous slot 3 Mill slot 5 Gauzed wrapped XXX Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)																																																																													
SCREEN-PERFORATED INTERVALS: From 65' ft. to 75' ft. From ft. to ft. From ft. to ft. From ft. to ft.																																																																													
GRAVEL PACK INTERVALS: From ft. to ft. From ft. to ft. From 75' ft. to 21' ft. From ft. to ft.																																																																													
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite XX 4 Other																																																																													
Grout Intervals: From 21' ft. to 2' ft. From ft. to ft. From ft. to ft.																																																																													
What is the nearest source of possible contamination:																																																																													
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 15 Oil well/Gas well XX 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 16 Other (specify below) Direction from well? North East How many feet? 60'																																																																													
<table border="1"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>0'</td><td>3'</td><td>Top Soil</td><td></td><td></td><td></td></tr><tr><td>3'</td><td>5'</td><td>Sandy Clay.</td><td></td><td></td><td></td></tr><tr><td>5'</td><td>21'</td><td>Brown Clay.</td><td></td><td></td><td></td></tr><tr><td>21'</td><td>23'</td><td>Fine Sand.</td><td></td><td></td><td></td></tr><tr><td>23'</td><td>31'</td><td>Sandy ClayW/Course Sand.</td><td></td><td></td><td></td></tr><tr><td>31'</td><td>35'</td><td>Fine Cemented Sand.</td><td></td><td></td><td></td></tr><tr><td>35'</td><td>43'</td><td>Medium Course Sand(Red).</td><td></td><td></td><td></td></tr><tr><td>43'</td><td>48'</td><td>Grey Clay.</td><td></td><td></td><td></td></tr><tr><td>48'</td><td>61'</td><td>Medium Fine Sand.</td><td></td><td></td><td></td></tr><tr><td>61'</td><td>75'</td><td>Course Sand & Gravel (Clean).</td><td></td><td></td><td></td></tr><tr><td></td><td></td><td>Clay.</td><td></td><td></td><td></td></tr></tbody></table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0'	3'	Top Soil				3'	5'	Sandy Clay.				5'	21'	Brown Clay.				21'	23'	Fine Sand.				23'	31'	Sandy ClayW/Course Sand.				31'	35'	Fine Cemented Sand.				35'	43'	Medium Course Sand(Red).				43'	48'	Grey Clay.				48'	61'	Medium Fine Sand.				61'	75'	Course Sand & Gravel (Clean).						Clay.			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																																								
0'	3'	Top Soil																																																																											
3'	5'	Sandy Clay.																																																																											
5'	21'	Brown Clay.																																																																											
21'	23'	Fine Sand.																																																																											
23'	31'	Sandy ClayW/Course Sand.																																																																											
31'	35'	Fine Cemented Sand.																																																																											
35'	43'	Medium Course Sand(Red).																																																																											
43'	48'	Grey Clay.																																																																											
48'	61'	Medium Fine Sand.																																																																											
61'	75'	Course Sand & Gravel (Clean).																																																																											
		Clay.																																																																											
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) Sept. 13 1999 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 112 This Water Well Record was completed on (mo/day/yr) Sept. 17 1999 under the business name of Wells Drilling Co. by (signature) Dal Wells																																																																													
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.																																																																													