

MW#9

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Sedgwick</u>		<u>NE 1/4 NE 1/4 SE 1/4</u>	<u>3025</u>	T <u>27</u> S	R <u>1</u> 20
Distance and direction from nearest town or city street address of well if located within city? <u>851 1001 S. Meridian, Wichita, KS.</u>					
2 WATER WELL OWNER: <u>Town + Country Markets</u>					
RR#, St. Address, Box #: <u>P.O. Box 17087</u>				Board of Agriculture, Division of Water Resources	
City, State, ZIP Code: <u>Wichita KS 67217</u>				Application Number:	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>25</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. <u>17</u> ft. 2. <u>17</u> ft. 3. <u>17</u> ft.			
		WELL'S STATIC WATER LEVEL <u>17</u> ft. below land surface measured on mo/day/yr <u>8-24-00</u>			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter: <u>7 1/4</u> in. to <u>25</u> ft., and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only <u>10</u> Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No <u>(X)</u> If yes, mo/day/yr sample was submitted _____			
		Water Well Disinfected? Yes _____ No _____			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued _____ Clamped _____ <u>10</u> PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded _____ 7 Fiberglass Threaded <u>X</u>					
Blank casing diameter <u>2</u> in. to <u>15</u> ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.					
Casing height above land surface <u>0</u> in., weight <u>Sched 40</u> lbs./ft. Wall thickness or gauge No. _____					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) _____ 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot <u>10</u> Mill slot <u>0.10</u> 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) _____					
SCREEN-PERFORATED INTERVALS: From <u>25</u> ft. to <u>15</u> ft., From _____ ft. to _____ ft.					
From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From <u>25</u> ft. to <u>13</u> ft., From _____ ft. to _____ ft.					
From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement <u>10</u> Cement grout <u>10</u> Bentonite 4 Other _____					
Grout Intervals: From <u>2</u> ft. to <u>0</u> ft., From <u>13</u> ft. to <u>2</u> ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well <u>10</u> Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) _____ 13 Insecticide storage					
Direction from well? <u>North</u> How many feet? <u>15'</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
<u>0</u>	<u>3</u>	<u>Topsoil Dark Bm</u>			
<u>3</u>	<u>7</u>	<u>Bm Silty Clay</u>			
<u>7</u>	<u>11</u>	<u>Silty slightly sandy clay</u>			
		<u>Tan Bm</u>			
<u>11</u>	<u>15</u>	<u>Tan fine to medium</u>			
		<u>clayey sand</u>			
<u>15</u>	<u>20</u>	<u>Fine to medium sand tan</u>			
		<u>saturated @ 16-17</u>			
<u>20</u>	<u>25</u>	<u>medium to coarse sand</u>			
		<u>with increasing grain size</u>			
		<u>w/ depth</u>			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>10</u> constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>4-24-00</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>575</u> This Water Well Record was completed on (mo/day/yr) <u>4-25-00</u>					
under the business name of <u>FUNKIE DRILLING SERVICE</u> by (signature) <u>Allen L. Kuntz</u>					