

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

40,926 & 30,352

1 LOCATION OF WATER WELL:

County: Sedgwick

Fraction

SE 1/4 SW 1/4 NW 1/4

Section Number

31

Township Number

T 27 S

Range Number

R 1 E W

Distance and direction from nearest town or city street address of well if located within city? Approximately 1/8 mile southeast of the intersection of Dora Street and 119th Street in Wichita

Global Positioning Systems (decimal degrees, min. of 4 digits)

Latitude: 37.657467

Longitude: -97.477928

Elevation: Unknown

Datum: NAD83

Data Collection Method: WAAS GPS Unit

2 WATER WELL OWNER: City of Goddard

RR#, St. Address, Box # : 118 N. Main
City, State, ZIP Code : P.O. Box 667
Goddard, KS 67052

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

N	
--NW--	--NE--
x	
--SW--	--SE--
S	

4 DEPTH OF COMPLETED WELL

136.61 ft.

Depth(s) Groundwater Encountered (1) ft. (2) ft. (3) ft.

WELL'S STATIC WATER LEVEL 26 ft. below land surface measured on mo/day/yr 12-12-06

Pump test data: Well water was Not checked ft. after hours pumping gpm

Est. Yield Unknown gpm: Well water was ft. after hours pumping gpm

WELL WATER TO BE USED AS: (5) Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr

Sample was submitted

Water well disinfected? Yes ☒ No

5 TYPE OF CASING USED:

(1) Steel

3 RMP (SR)

5 Wrought Iron

8 Concrete tile

CASING JOINTS: Glued ☒ Clamped

(2) PVC

4 ABS

7 Fiberglass

6 Asbestos-Cement

9 Other (specify below)

Bolted ☒ Welded ☒

Threaded

Blank casing diameter 16 in. to 31.24 (steel) ft., Diameter 16 in. to 78.29 (PVC) ft., Diameter 16 in. to 131.11 (PVC) ft.

Casing height above land surface 0 in., weight 62.58 Steel/25.55 PVC lbs./ft. Wall thickness or gauge No. .375 Steel/.843 PVC

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel

(3) Stainless Steel

5 Fiberglass

7 PVC

9 ABS

11 Other (Specify)

2 Brass

4 Galvanized Steel

6 Concrete tile

8 RM (SR)

10 Asbestos-Cement

12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

(1) Continuous slot

3 Mill slot

5 Gauzed wrapped

7 Torch cut

9 Drilled holes

11 None (open hole)

2 Louvered shutter

4 Key punched

6 Wire wrapped

8 Saw Cut

10 Other (Specify)

SCREEN-PERFORATED INTERVALS: From 78.29 ft. to 112.96 ft., From ft. to ft.

From 131.11 ft. to 137.11 ft., From ft. to ft.

GRAVEL PACK INTERVALS: From 35 ft. to 140 ft., From ft. to ft.

From ft. to ft., From ft. to ft.

6 GROUT MATERIAL:

1 Neat Cement

(2) Cement grout

3 Bentonite

(4) Other

Bentonite Holeplug

Compacted Soil

Grout Intervals: From 0 ft. to 5 ft., From 5 ft. to 25 ft., From 25 ft. to 35 ft.

What is the nearest source of possible contamination:

1 Septic tank

4 Lateral lines

7 Pit privy

10 Livestock pens

13 Insecticide Storage

(16) Other (specify below)

2 Sewer lines

5 Cess pool

8 Sewage lagoon

11 Fuel storage

14 Abandoned water well

None known

3 Watertight sewer lines

6 Seepage pit

9 Feedyard

12 Fertilizer Storage

15 Oil well/gas well

Direction from well?

How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil	44	49	Sand and gravel, fine to medium
3	7	Clay, dark gray, hard	49	54	Sand, fine to very fine
7	13	Clay, brown, sandy	54	66	Clay, green and gray
13	18	Sand and gravel, fine to medium, coarse	66	74	Sand, very fine, with clay, gray
18	19	Clay, tan	74	78	Sand, very fine, some clay
19	23	Sand and gravel, fine to medium, coarse	78	84	Sand, very fine to fine
23	24	Clay, tan	84	91	Sand, fine to medium, coarse
24	28	Sand and gravel, fine to medium, some coarse	91	95	Sand, fine to medium
			95	111	Sand and gravel, fine to medium
28	36	Sand and gravel, fine to medium	111	111.5	Clay
36	44	Clay, gray, with sand, fine	111.5	115	Sand and gravel, fine to medium

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:

This water well was (1) constructed (2) reconstructed (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-12-06 and this record is true to the best of my knowledge and belief.

Kansas Water Well Contractor's License No. 185

This Water Well Record was completed on (mo/day/year) 12-20-06

Under the business name of Clarke Well & Equipment, Inc.

by (signature)

James W. Clark

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

Form WWC-5

40,926 & 30,352

[illegible]