

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Sedgwick Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ . Former Amoco #7402 3935 West 13th Street, Wichita, KS 67203	Fraction NE ¼ NE ¼ NE ¼ NE ¼	Section Number 12 13	Township No. T 27 S	Range Number R 1 ☐ E ☒ W								
2 WATER WELL OWNER: Amoco Oil Company RR#, Street Address, Box #: 1701 Summit Avenue City, State, ZIP Code : Plano, TX 75074		Global Positioning System (GPS) information: Latitude: 37.71436 (in decimal degrees) Longitude: 97.39406 (in decimal degrees) Elevation: 1314.09 Datum: ☒ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☒ Land Survey Est. Accuracy: ☒ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m										
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="width: 100%; text-align: center; border-collapse: collapse;"> <tr> <td style="width: 25%;">NW</td> <td style="width: 25%;">NE</td> <td style="width: 25%;">SE</td> <td style="width: 25%;">SW</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </table> S -----1 mile-----	NW	NE	SE	SW					4 DEPTH OF COMPLETED WELL 23 ft. Depth(s) Groundwater Encountered (1) 18 ft. (2) N/A ft. (3) N/A ft. WELL'S STATIC WATER LEVEL 17.74 ft. below land surface measured on mo/day/yr. 1/7/2013 Pump test data: Well water was N/A ft. after N/A hours pumping. N/A gpm EST. YIELD N/A gpm. Well water was N/A ft. after N/A hours pumping. N/A gpm Bore Hole Diameter 8.25 in. to 23 ft. and N/A in. to N/A ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☒ Monitoring well MW-13R Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted N/A Water well disinfected? ☐ Yes ☒ No			
NW	NE	SE	SW									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded Casing diameter 2 in. to 13 ft., Diameter N/A in. to N/A ft., Diameter N/A in. to N/A ft. Casing height above land surface 0 in., Weight N/A lbs./ft., Wall thickness or gauge No. Schedule 40 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 13 ft. to 23 ft., From N/A ft. to N/A ft. From N/A ft. to N/A ft., From N/A ft. to N/A ft. GRAVEL PACK INTERVALS: From 11 ft. to 23 ft., From N/A ft. to N/A ft. From N/A ft. to N/A ft., From N/A ft. to N/A ft.												
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other 0-2 Concrete Grout Intervals: From 2 ft. to 11 ft., From N/A ft. to N/A ft., From N/A ft. to N/A ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☒ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well East Distance from well <150 feet												
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS							
0	2	Silty CLAY, dark brown, slightly moist, medium stiff, trace plstctv										
2	8	Sandy CLAY, yellowish brown slightly moist, medium stiff, trace plstctv.										
8	17	Fine SAND, light brown, slightly moist										
17	23	Coarse to very coarse SAND, light brown very wet										
	23	Boring terminated.										
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 1/7/2013 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 759 This Water Well Record was completed on (mo/day/year) 2/4/2013 under the business name of RAZEK Environmental, LLC by (signature) <i>[Signature]</i> INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .												