


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction ☒ NW 1/4 SW 1/4 SW 1/4	Section number 2	Township number T 27 S R 1W E W	Range number EW
2. Distance and direction from nearest town or city: 1/2 mile East of Hoover Road on 21st St. on the North Side. Wichita, Kansas			3. Owner of well: Big River Sand Co. R.R. or street: Box 9090 City, state, zip code: Wichita, Kansas		
4. Locate with "X" in section below: 			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 1-17-79 Well depth 45 ft.
Topsoil			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Sandy clay			2	12	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☒ Other
Medium sand			12	20	9. Casing: Material PVC Height: Above or below 464 Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight 3.96 lbs./ft. Dia. 6 in. to 45 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 316
Medium to coarse sand with some gravel			20	31	10. Screen: Manufacturer's name PVC NSF approved 200 PSI Type PVC 200 PSI Dia. 6" Slot/gage .06 Length 20' Set between 25 ft. and 45 ft. ft. and ☐ ft. Gravel pack ☒ yes Size range of material 1/2-1/8"
Coarse sand and gravel			31	45	11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 1-18-79
					12. Pumping level below land surfaces: ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
					☒ Water sample submitted: ☐ mo./day/yr. Yes ☒ No Date ☐
					14. Well head completion: ☒ Pitless adapter 12 inches above grade
					15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.
					16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type None Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: Manufacturer's name Jacuzzi Not installed Model number 3S6B3 HP 3 Volts 440 Length of drop pipe 30 ft. capacity 70 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification:		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	From #8 above: Supplies water for bearings on sand auger. No apparent source for contamination.		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Arnold Date 2-28-79 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5