


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SW 1/4 NW 1/4 SE 1/4	Section number 3	Township number T 27 S R 1	Range number 4W	
2. Distance and direction from nearest town or city: North of 21st between Hoover Rd & Ridge Rd. Street address of well location if in city:			3. Owner of well: Allen's Concrete R.R. or street: Wichita, Kansas City, state, zip code:				
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		Well No. 1 (TH 1-77)			
5. Type and color of material			From	To	6. Bore hole dia. 17 in. Completion date 3-15-77 Well depth 34 ft.		
Top soil			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
Fine to coarse sand			2	4	8. Use: ☐ Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Brown clay			4	7	9. Casing: Material Steel Height: Above ☐ below ☒ Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 8 in. to 30 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 277		
Fine to coarse sand & gravel			7	24	10. Screen: Manufacturer's name Layne Stainless Type Steel Dia. 8" Slot/gauze ☐ Length 5' Set between 29 ft. and 34 ft. ☐ ft. and ☐ ft. Gravel pack? yes Size range of material 1/8 x 1/2		
Tan clay			24	27	11. Static water level: ☐ mo./day/yr. 10.7 ft. below land surface Date 3/10/77		
Med. to coarse sand & gravel			27	35	12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
					13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
					14. Well head completion: ☐ Pitless adapter 12 inches above grade		
					15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
					16. Nearest source of possible contamination: Inside ft. 0.5 Direction West Type Sanitary Line Well disinfected upon completion? ☒ Yes ☐ No		
					17. Pump: ☐ Not installed Manufacturer's name Layne Model number BURHC HP 5 Volts 230/460 Length of drop pipe 25 ft. capacity 100 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
(Use a second sheet if needed)							
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley		19. Remarks: Well for washing gravel		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. 3/28/77 Address Wichita, Kansas Signed [Signature] Date 3/28/77 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Farm WWC-5