

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NE 1/4 SW 1/4	Section number 8	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: R.R. or street: City, state, zip code:			
#2 North well Armarado Estates			L. E. Richards 230 South Market Wichita, Kansas 67202			
4. Locate with "X" in section below: N W E S 1 Mile Sketch map: 13 & Maize Road, Wichita, Kansas			6. Bore hole dia. 1 1/2 in. Completion date 5-2-77 Well depth 136 ft.			
			7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other			
			9. Casing: Material PVC Height: Above or below 12 in. Threaded ☐ Welded ☐ Surface 12 in. RMP 8 PVC ☒ Weight 5.47 lbs./ft. Dia. 8 in. to 136 ft. depth Wall Thickness 3/32 inches or Dia. 8 in. to 136 ft. depth gage No. 332			
			10. Screen: Manufacturer's name PVC NSF approved 160 PSI Type PVC 160 PSI Dia. 8" Slot/groove .06 Length 10' Set between 126 ft. and 136 ft. Gravel pack? yes Size range of material 1/4-1/8"			
5. Type and color of material			From	To	11. Static water level: 26 ft. below land surface Date 5-2-77 mo./day/yr.	
Topsoil			0	2	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.	
Clay			2	18	13. Water sample submitted: ____ mo./day/yr. ☐ Yes ☐ No Date ____	
Sandy Clay			18	25	14. Well head completion: 12 ☒ Pitless adapter ____ Inches above grade	
Fine Sand			25	45	15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
Fine Sand with Clay Streaks			45	60	16. Nearest source of possible contamination: NONE ft. ____ Direction ____ Type ____ Well disinfected upon completion? ☒ Yes ☐ No	
Clay			60	84	17. Pump: Pioneer Pump Not installed Manufacturer's name P160 HP 7 1/2 Volts 230 Model number 50 ft. capacity 115 g.p.m. Length of drop pipe ____ ft. capacity ____ g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
Fine Sand			84	96		
Clay			96	108		
Fine Sand			108	120		
Medium Sand			120	125		
Coarse Sand with Some Gravel			125	136		
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		Flat Ground No apparent source for contamination. Well to be for sprinkler system		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump Serv. 236 Business name Wichita, Kansas License No. ____ Address M. Arnold Signed M. Arnold Date 11-30-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5