


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NE 1/4 NW 1/4	Section number 14	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: R.R. or street: City, state, zip code:			
1215 Smith Wichita, Kansas			Vonna Lenz 1215 Smith Wichita, Kansas			
4. Locote with "X" in section below: Sketch map: 			6. Bore hole dia. 11 in. Completion date _____ Well depth 40 ft. 7-18-78			
5. Type and color of material			From	To	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Sandy Topsoil			0	2	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Brown Clay			2	9	9. Casing: Material styrene Height: Above or below _____ Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight _____ lbs./ft. Dia. 5 in. to 40 ft. depth Wall Thickness: inches or _____ Dia. _____ in. to _____ ft. depth gage No. 200	
Fine Sand			9	20	10. Screen: Manufacturer's name _____ Sunflower Plastic Type Styrene Dia. 5" Slot 1/16 .06 Length 15' Set between 25 ft. and 40 ft. _____ ft. and _____ ft. Gravel pack? yes Size range of material 1/4-1/8"	
Coarse Sand			20	40	11. Static water level: _____ mo./day/yr. 16 ft. below land surface Date 7-18-78	
					12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
					13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☐ No Date _____	
					14. Well head completion: ☒ Pitless adapter 12 inches above grade	
					15. Well grouted? yes 1-2 Fine Sand Mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
					16. Nearest source of possible contamination: City _____ ft. 100 Direction West Type Sewer Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: _____ Not installed Manufacturer's name Sta-Rite Model number 20P4C02 HP 1/2 Volts 230 Length of drop pipe 30 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
			(Use a second sheet if needed)			
18. Elevation:		19. Remarks: Flat Ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Arnold Date 8-1-78 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5