

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Sedgwick		SE 1/4 SW 1/4 SE 1/4	16	T 27 S	R 1 E
Distance and direction from nearest town or city street address of well if located within city? 768 Brownthrusch					

2 WATER WELL OWNER: Smith, Robert		Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: 768 Brownthrusch		Application Number: N.A.
City, State, ZIP Code: Wichita KS 67212		

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 55 ft. ELEVATION:	
		Depth(s) Groundwater Encountered 1. 33 ft. 2. ft. 3. ft.	
		WELL'S STATIC WATER LEVEL 33 ft. below land surface measured on mo/day/yr	
		Pump test data: Well water was 35 ft. after 2 hours pumping 10 gpm	
		Est. Yield 50 gpm: Well water was ft. after hours pumping gpm	
		Bore Hole Diameter: 9 in. to 13 ft., and 6 in. to 55 ft.	
WELL WATER TO BE USED AS:			
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial ⑦ Lawn and garden only 10 Observation well			
Was a chemical/bacteriological sample submitted to Department? Yes.....No X; If yes, mo/day/yr sample was submitted			
Water Well Disinfected? Yes No			

5 TYPE OF BLANK CASING USED:		5 Wrought iron		8 Concrete tile		CASING JOINTS: Glued X .. Clamped	
1 Steel		③ RMP (SR)		6 Asbestos-Cement		9 Other (specify below)	
2 PVC		4 ABS		7 Fiberglass		Welded	
Blank casing diameter 6 in. to 50 ft., Dia. in. to ft., Dia. in. to ft.						Threaded	
Casing height above land surface 12 in., weight lbs./ft. Wall thickness or gauge No. 200							
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC		10 Asbestos-cement			
1 Steel		3 Stainless steel		5 Fiberglass		⑧ RMP (SR)	
2 Brass		4 Galvanized steel		6 Concrete tile		9 ABS	
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped		⑧ Saw cut		11 None (open hole)	
1 Continuous slot		3 Mill slot		6 Wire wrapped		9 Drilled holes	
2 Louvered shutter		4 Key punched		7 Torch cut		10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 50 ft. to 55 ft., From ft. to ft.							
GRAVEL PACK INTERVALS: From ft. to ft., From ft. to ft.							

6 GROUT MATERIAL:		1 Neat cement		2 Cement grout		③ Bentonite		4 Other	
Grout Intervals: From 3 ft. to 13 ft., From ft. to ft., From ft. to ft.									
What is the nearest source of possible contamination:		10 Livestock pens		14 Abandoned water well					
1 Septic tank		4 Lateral lines		7 Pit privy		11 Fuel storage		15 Oil well/Gas well	
2 Sewer lines		5 Cess pool		8 Sewage lagoon		12 Fertilizer storage		16 Other (specify below)	
③ Watertight sewer lines		6 Seepage pit		9 Feedyard		13 Insecticide storage			
Direction from well? South						How many feet? 12			

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	7	LT. Brn sand/clay 10am			
7	16	Reddish Brn sand/clay 10am			
16	20	LT Tan clay			
20	25	Drk Brn sand/clay 10am			
25	27	Drk Brn clay			
27	33	LT Brn med. Sand			
33	41	LT Brn coarse gravel			
41	45	BLK med coarse sand			
45	50	yellow clay balls			
50	55	LT Brn med. Sand			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) Oct. 15, 1983 and this record is true to the best of my knowledge and belief. Kansas	
Water Well Contractor's License No. 295 This Water Well Record was completed on (mo/day/yr)	
under the business name of Protheroe Pump & Well Service by (signature) <i>Thom P. Protheroe</i>	

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY

T

27

R

1

E

SEC.

16

SE 1/4

SW 1/4

SE 1/4