


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGEBWICK	Fraction SW 1/4 SW 1/4 SE 1/4	Section number 16	Township number T 27	Range number S R 1 W	E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: 7534 COTTON TAIL				3. Owner of well: HENRY GUERRERO R.R. or street: 7534 COTTON TAIL City, state, zip code: WICHITA, KS.			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 8 in. Completion date 6-1-77 Well depth 100 ft.			
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other	
0-15 Topsoil		0		15		9. Casing: Material Steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 6.5 lbs./ft. Dia. 5 in. to 100 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 300 MNC	
FINE SAND		16		75		10. Screen: Manufacturer's name J&L Type 200 Dia. 5 1/4 Slot/gauze .065 Length 10 Set between 90 ft. and 100 ft. Gravel pack? YES Size range of material 1/4-3/4	
GRAVEL - COARSE		76		100		11. Static water level: 35 ft. below land surface Date 5-25-77 mo./day/yr.	
						12. Pumping level below land surfaces: 35 ft. after 1 hrs. pumping 15 g.p.m. 40 ft. after 2 hrs. pumping 20 g.p.m. Estimated maximum yield 30 g.p.m.	
						13. Water sample submitted: YES mo./day/yr. Yes ☒ No ☐ Date	
						14. Well head completion: ☐ Pitless adapter 12 1/4 Inches above grade	
						15. Well grouted? YES With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
						16. Nearest source of possible contamination: ft. 60 Direction E Type SEWER Well disinfected upon completion? ☒ YES ☐ NO	
						17. Pump: Manufacturer's name Dempster Not installed Model number DA75S2 HP 3/4 Volts 220 Length of drop pipe 75 ft. capacity 15 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. 21ST ELECTRIC 129 Business name 512 W. 24th License No. Address J. Hanks Date 6-8-77 Signed J. Hanks Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5