


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

NW NE SE NW

1. Location of well:	County Sedgwick	Fraction 1/4 NE 1/4 NW 1/4	Section number 20	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: 451 Fairway, Wichita, Kansas Street address of well location if in city:		3. Owner of well: Jim Menesco R.R. or street: 451 Fairway City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. 11 in. Completion date 9-25-78 Well depth 120 ft.	
5. Type and color of material		From	To	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Topsoil		0	3	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other	
Clay		3	15	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 120 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200	
Fine sand		15	50	10. Screen: Manufacturer's name Sunflower plastic	
Medium sand with clay balls		50	68	Type styrene Dia. 5" Slot .06 Length 25' Set between 95 ft. and 120 ft. ft. and ft. Gravel pack? yes Size range of material 1/2-1/8"	
Fine sand		68	92	11. Static water level: 25 ft. below land surface Date 9-25-78 mo./day/yr.	
Medium sand		92	120	12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.	
				13. Water sample submitted: Yes ☐ No ☐ Date	
				14. Well head completion: ☒ Pitless adapter 12 Inches above grade	
				15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
				16. Nearest source of possible contamination: City ft. 75 Direction South Type Sewer Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: ☐ Not installed Manufacturer's name Sta-rite Model number 40 Series HP 2 Volts 230 Length of drop pipe 50 ft. capacity 35 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
		(Use a second sheet if needed)			
18. Elevation:	19. Remarks: Flat ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 10-24-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5