

LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number
County: <u>Sedgewick</u>		<u>SW 1/4 SE 1/4 NE 1/4</u>	<u>20</u>	<u>T 27 S</u>	<u>R 1 E W</u>
Distance and direction from nearest town or city street address of well if located within city? <u>#5 Rolling Hills Wichita KS</u>					
WATER WELL OWNER:			Board of Agriculture, Division of Water Resources		
RR#, St. Address, Box # : <u>#5 Rolling Hills</u>			Application Number:		
City, State, ZIP Code : <u>Wichita KS 67209</u>					
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		DEPTH OF COMPLETED WELL <u>54</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. <u>22</u> ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL <u>22</u> ft. below land surface measured on mo/day/yr <u>7-6-83</u>			
		Pump test data: Well water was <u>22</u> ft. after <u>1/2</u> hours pumping <u>20</u> gpm			
		Est. Yield <u>50</u> gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter <u>1 1/2</u> in. to <u>54</u> ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		☒ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Lawn and garden only ☐ Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No... ☒ ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes ☒ No			
TYPE OF BLANK CASING USED:		CASING JOINTS: Glued ☒ Clamped			
1 Steel		3 RMP (SR)		Welded ☒	
2 PVC		4 ABS		Threaded	
Blank casing diameter <u>1 1/2</u> in. to <u>42</u> ft., Dia. in. to ft., Dia. in. to ft.					
Casing height above land surface <u>12</u> in., weight <u>1.59</u> lbs./ft. Wall thickness or gauge No. <u>SDR-26</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC			
1 Steel		3 Stainless steel		10 Asbestos-cement	
2 Brass		4 Galvanized steel		11 Other (specify)	
SCREEN OR PERFORATION OPENINGS ARE:		5 Fiberglass		12 None used (open hole)	
1 Continuous slot		6 Concrete tile			
☒ 3 Mill slot		5 Gauzed wrapped		8 Saw cut	
2 Louvered shutter		6 Wire wrapped		11 None (open hole)	
4 Key punched		7 Torch cut		9 Drilled holes	
SCREEN-PERFORATED INTERVALS:		10 Other (specify)			
From <u>42</u> ft. to <u>54</u> ft., From ft. to ft.					
GRAVEL PACK INTERVALS:					
From <u>13</u> ft. to <u>54</u> ft., From ft. to ft.					
FROM ft. to ft., FROM ft. to ft.					
GROUT MATERIAL:		4 Other			
1 Neat cement		2 Cement grout		3 Bentonite	
Grout Intervals: From <u>3</u> ft. to <u>13</u> ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:		How many feet? <u>90</u>			
☒ Septic tank		10 Livestock pens			
4 Lateral lines		14 Abandoned water well			
2 Sewer lines		11 Fuel storage			
5 Cess pool		15 Oil well/Gas well			
3 Watertight sewer lines		12 Fertilizer storage			
6 Seepage pit		16 Other (specify below)			
Direction from well? <u>West.</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
<u>0</u>	<u>2</u>	<u>Top soil</u>			
<u>2</u>	<u>11</u>	<u>clay</u>			
<u>11</u>	<u>20</u>	<u>fine sand</u>			
<u>20</u>	<u>48</u>	<u>gravel</u>			
<u>48</u>	<u>50</u>	<u>clay</u>			
<u>50</u>	<u>54</u>	<u>med sand</u>			
CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>7-6-83</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>318</u> . This Water Well Record was completed on (mo/day/yr) <u>7-7-83</u> under the business name of <u>Wenger Drilling</u> by (signature) <u>[Signature]</u>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					