


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 SW 1/4 SW 1/4	Section number 20	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: Well #1 Street address of well location if in city: Maple & Maize Road Wichita, Kansas			3. Owner of well: Maple Gardens Retirement Center R.R. or street: 601 Hidden Valley Road City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. 30 in. Completion date 12-20-77 Well depth 160 ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Brown Sandy Clay		0	11	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☒ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Medium-to Coarse Sand and Gravel		11	16	9. Casing: Material Transite Height: Above or below SEE #19 ☒ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight 37 lbs./ft. Dia. 16 in. to 160 ft. depth Wall Thickness: inches 3/4 Dia. ☐ in. to ☐ ft. depth Gauge No. ☐		
Blue Clay		16	29	10. Screen: Manufacturer's name Johnson Type irrigator Dia. 16" Slot/gage .100 Length 20' Set between 140 ft. and 160 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 1/4-1/8		
Fine to Coarse Sand and Medium Gravel		29	54	11. Static water level: ☐ mo./day/yr. 16 ft. below land surface Date 12-20-77		
Clay		54	57	12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
Fine to Coarse Sand and Gravel		57	79	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☐ No Date ☐		
Clay		79	105	14. Well head completion: 12 capped ☐ Pitless adapter ☐ inches above grade		
Fine Sand		105	109	15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
Fine to Coarse Sand with some Clay		109	134	16. Nearest source of possible contamination: City ft. 300 Direction South Type Sewer Well disinfected upon completion? ☒ Yes ☐ No		
Medium to Coarse Sand and Gravel		134	160	17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
(Use a second sheet if needed)						
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: Flat Ground From #9 Banded But Joint			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name Wichita, Kansas License No. ☐ Address ☐ Signed M. Arnold Date 12-31-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5