

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

NE NE NW SW

1. Location of well: County JEDGWICK		Fraction 1/4 SE 1/4 NW 1/4	Section number 21	Township number T 27 S	Range number R 1 E
2. Distance and direction from nearest town or city: 258 N. EVERGREEN			3. Owner of well: MICHAEL SABALA		
Street address of well location if in city: WICHITA, KANSAS			City, state, zip code: WICHITA, KANSAS		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 12.5 in. Completion date 10-12-76	
				Well depth 125 ft.	
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug	
				☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry	
				☐ Irrigation ☐ Air conditioning ☐ Stock	
				☐ Lawn ☐ Oil field water ☐ Other	
				9. Casing: Material STYRENE Weight: 50 lbs./ft.	
				Threaded ☐ Welded ☒ Surface 12 in.	
				RMP ☒ PVC ☐ Weight 106 lbs./ft.	
				Dia. 5 in. to 125 ft. depth Wall Thickness: 1/2 inches or	
				Dia. 5 in. to 125 ft. depth gage No. 200	
5. Type and color of material		From	To	10. Screen: Manufacturer's name SUNFLOWER PLASTIC	
TOPSOIL		0	2	Type STYRENE Dia. 5"	
SANDY SOIL		2	16	Slot/gauze 106 Length 25'	
FINE SAND		16	35	Set between 100 ft. and 125 ft.	
FINE SAND WITH CLAY BALLS		35	50	Gravel pack? YES Size range of material 1/4-1/8"	
MIXED THROUGH SAND				11. Static water level: 28 ft. below land surface Date 10-12-76	
FINE SAND		50	90	12. Pumping level below land surfaces:	
MEDIUM COARSE SAND		90	125	☐ ft. after ☐ hrs. pumping ☐ g.p.m.	
				☐ ft. after ☐ hrs. pumping ☐ g.p.m.	
				Estimated maximum yield ☐ g.p.m.	
				13. Water sample submitted: ☐ Yes ☐ No Date ☐	
				14. Well head completion: ☒ Pitless adapter 12 inches above grade	
				15. Well grouted? YES	
				With: ☐ Neat cement ☐ Bentonite ☒ Concrete	
				Depth: From 40" to 14 ft.	
				16. Nearest source of possible contamination: CITY SEWER	
				ft. 80 Direction EAST Type SEWER	
				Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: ☐ Not installed	
				Manufacturer's name SEARS	
				Model number N/A HP 3/4 Volts 230	
				Length of drop pipe 50 ft. capacity 20 g.p.m.	
				Type: ☒ Submersible ☐ Turbine	
				☐ Jet ☐ Reciprocating	
				☐ Centrifugal ☐ Other	
18. Elevation:		19. Remarks: FLAT GROUND		20. Water well contractor's certification:	
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley		INSTALLED CUSTOMERS PUMP.		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.	
				Business name HARP WELL & PUMP License No. 236	
				Address WICHITA, KANSAS	
				Signed DA Arnold Date 10-15-76	
				Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5