


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

RE CONSTRUCTION

OK. DWIGHT BRINKLEY 7/5/77

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County SEDGWICK	Fraction SW 1/4 BE 1/4 NE 1/4	Section number 22	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city:	Street address of well location if in city: 560 BOYD WICHITA, KANS		3. Owner of well: BERT WAYMIRE R.R. or street: 140N BLECKLEY DRIVE City, state, zip code: WICHITA KANS 67208		
4. Locate with "X" in section below:	Sketch map: 		PULLED 24' DRIVEN WELL - REAMED HOLE TO 8" TO STATIC LEVEL AT 11.5' DROVE 4" CASING INTO WBT SAND 1 FOOT. DROVE WELL TO COMPLETION AT 30 FT. GROUTED CASING TO STATIC LEVEL		
5. Type and color of material	From		To		
TOP SOIL SANDY BLACK		0	3		
SAND MEDIUM TAN		3	6		
SAND MEDIUM RED		6	8		
SAND GRAY - BITS OF BLACK CLAY		8	9		
SAND MEDIUM REDDISH		9	11.5		
H ₂ O DROVE 1 1/4 GALL.			11.5		
PIPE 4 POINT TO			30		
6. Bore hole dia. 8 in. Completion date 7-6-77 Well depth 30 ft. FROM GROUND LEVEL					
7. ☐ Cable tool ☐ Rotary ☒ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☐ Reverse rotary					
8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other					
9. Casing: Material RMP Height: Above or below Threaded 504 Welded ☒ Surface 17 in. RMP ☒ PVC Weight 1.35 lbs./ft. Dia. 4 in. to 13.5 ft. depth Wall Thickness: inches or Dia. 4 in. to 13.5 ft. depth gage No. 1200					
10. Screen: Manufacturer's name CLAYTON MARK Type BRASS Dia. 1.25 Slot/gauze .060 Length 4 FT. Set between 26 ft. and 30 ft. Gravel pack? NO Size range of material					
11. Static water level: 11.5 ft. below land surface Date 7-6-77 mo./day/yr.					
12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping NA g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield 40 g.p.m.					
13. Water sample submitted: ____ mo./day/yr. Yes ☐ No ☒ Date					
14. Well head completion: ____ Pitless adapter 12 inches above grade					
15. Well grouted? YES With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 11.5 ft.					
16. Nearest source of possible contamination: ft. 3 Direction SO. Type CASE IRON SEWER Well disinfected upon completion? ☒ Yes ☐ No					
17. Pump: Not installed Manufacturer's name SEARS Model number NOT KNOWN HP 1/2 Volts 115 Length of drop pipe 30 ft. capacity 12 g.p.m. Type: ☒ Submersible ☐ Turbine ☒ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other					
(Use a second sheet if needed)					
18. Elevation: 1300 Topography: ☐ Hill ☐ Slope ☒ Upland ☒ Valley	19. Remarks: OWNER SIGNED STATEMENT HE WILL BUILD SLAB -				
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BEARDEN PUMP & WELL Business name WICHITA License No. 1/4 Address 312 MEYER Signed OT W Bearden Date 8-4 Authorized representative					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5