


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 NW 1/4 SE 1/4	Section number 26	Township number T 27 S	Range number R 1 W
2. Distance and direction from nearest town or city: 1313 Young Street address of well location if in city: Wichita, Kansas			3. Owner of well: Darrell Giller Plbg. R.R. or street: 625 North Parkwood City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 			
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 12-20-76 Well depth 50 ft.	
Sandy Topsoil			0	4	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Brown Clay			4	10	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand			10	30	9. Casing: Material styrene Above or below 11 Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 50 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200	
Medium Sand			30	50	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot 1/16" Length 15' Set between 35 ft. and 50 ft. Set between ☐ ft. and ☐ ft. Gravel pack? yes Size range of material 1/4-1/8"	
					11. Static water level: 18 ft. below land surface Date 12-20-76 mo./day/yr.	
					12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.	
					13. Water sample submitted: mo./day/yr. Yes ☐ No ☐ Date	
					14. Well head completion: 12 capped Pitless adapter 12 inches above grade	
					15. Well grouted? yes With: Neat cement ☐ Bentonite ☒ Concrete ☐ Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: City Wichita ft. 200 Direction East Type Sewer Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☒ Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
					(Use a second sheet if needed)	
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks: Flat Ground Well to be inside the building. Pump not installed at this time.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump236 Business name Wichita, Kansas License No. Address Signed M. Arnold Date 12-22-76 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5