

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 826-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDERWICK	Fraction NW 1/4 NE 1/4 NW 28	Section number 28	Township number T 27 S R 1 W E/W	Range number
2. Distance and direction from nearest town or city:			3. Owner of well: TED AUGUST			
Street address of well location if in city: 330 SO. SOCORRA			R.R. or street: 330 SO SOCORRA			
City, state, zip code: WICHITA KANS.			City, state, zip code: WICHITA KANS. -67209			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 9 in. Completion date 12-2-78		
		BORED 9" HOLE TO 13' - THEN 6" TO 28 FT. INSTALLED 5" CASING + USED SAND BUCKET TO COMPLETE AT 44' - GROUTED FROM -3 TO 13'		Well depth 44 ft.		
5. Type and color of material		From	To	7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☐ Reverse rotary		
TOP SOIL BLACK		0	3	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
CLAY BROWN		3	8	9. Casing: Material RMP Height: Above or below 12 in. Threaded 50 Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight 1.55 lbs./ft. Dia. 5 in. to 44 ft. depth Wall Thickness: inches or 0.200 Dia. 5 in. to 44 ft. depth gage No. 0.200		
CLAY BROWN RED		8	18	10. Screen: Manufacturer's name SUNFLOWER Type RMP Dia. 5 INCH Slot gauge 0.031 Length 9 FEET Set between 35 ft. and 44 ft. Gravel pack? NO Size range of material		
SAND YELLOW - MEDIUM		18	21	11. Static water level: 27.5 ft. below land surface Date 12-2-78 mo./day/yr.		
SAND BROWN COARSE		21	28	12. Pumping level below land surfaces: NA g.p.m. ft. after NA hrs. pumping NA g.p.m. ft. after NA hrs. pumping NA g.p.m. Estimated maximum yield 35 g.p.m.		
SAND TAN COARSE		28	44	13. Water sample submitted: NO Yes ☒ No ☐ Date		
				14. Well head completion: YES 12 inches above grade		
				15. Well grouted? YES With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 3 ft. to 13 ft.		
				16. Nearest source of possible contamination: 45 ft. Direction SO Type PLASTIC Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: Not installed Manufacturer's name FTW Model number 50AS HP 1/2 Volts 115 Length of drop pipe 39 ft. capacity 10 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation: 1300				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BEARDEN PUMP & WELL Business name 3142 MENTOR WICHITA KANS. Address John W. Bearden Signed 12-2-78 Date		
19. Remarks: CUSTOMER SIGNED STATEMENT HE WILL BUILD 4" X 4' X 4' REINFORCED CONCRETE SLAB AROUND WELL				Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5