

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction NW 1/4 NE 1/4 NE 1/4	Section number 28	Township number T 27 S R 1	Range number 1
2. Distance and direction from nearest town or city: Street address of well location if in city: 520 S. Holland				3. Owner of well: Ridge Plaza Park Wichita, Kansas R.R. or street: City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: Well No. 1		6. Bore hole dia. <u>12</u> in. Completion date <u>8/6/79</u> Well depth <u>102</u> ft.		
		7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary				
		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other				
		9. Casing: Material <u>PVC</u> Height: Above <u>12</u> in. Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>6</u> lbs./ft. Dia. <u>6</u> in. to <u>62</u> ft. depth Wall thickness: inches or Dia. <u>6</u> in. to <u>62</u> ft. depth gage No. <u>280</u>				
		10. Screen: Manufacturer's name <u>None</u> <u>1/8" saw slots</u> Type <u>PVC</u> Dia. <u>6"</u> Slot/gauze <u>1/8"</u> Length <u>40'</u> Set between <u>62</u> ft. and <u>102</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/8" x 3/8"</u>				
5. Type and color of material		From	To	11. Static water level: <u>34</u> ft. below land surface Date <u>8/6/79</u> mg./day/yr.		
Clay fill		0	3	12. Pumping level below land surfaces: <u>No Test</u> ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield <u>80</u> g.p.m.		
Red sandy clay		3	17	13. Water sample submitted: ____ Yes ☒ No Date ____ mo./day/yr.		
Fine to coarse sand & gravel		17	44	14. Well head completion: ☒ Pitless adapter <u>12</u> inches above grade		
Clay lens		44	46	15. Well grouted? <u>yes</u> With: ____ Neat cement ____ Bentonite ☒ Concrete Depth: From <u>5</u> ft. to <u>15</u> ft.		
Fine to coarse sand & gravel w/clay strks		46	102	16. Nearest source of possible contamination: <u>816g. South</u> ft. <u>50</u> Direction <u>South</u> Type <u>bidg. sewer</u> Well disinfected upon completion? ____ Yes ☒ No		
Tan clay w/sand streaks		102	110	17. Pump: ____ Not installed Manufacturer's name <u>Layne & Bowler</u> Model number <u>4RELC</u> HP <u>5</u> Volts <u>208</u> Length of drop pipe <u>84</u> ft. capacity <u>60</u> g.p.m. Type: ☒ Submersible ____ Turbine ____ Jet ____ Reciprocating ____ Centrifugal ____ Other		
Limestone		110	111	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name <u>Wichita, Kansas</u> License No. <u>8/6/79</u> Address <u>Wichita, Kansas</u> Signed <u>[Signature]</u> Date <u>8/6/79</u> Authorized representative		
Tan clay w/sand streaks		111	123			
Shale		123	135			
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: ____ Hill ____ Slope ☒ Upland ____ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5