

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Section NE 1/4 NE 1/4 NW 1/4	Section number 28	Township number T 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city:		517 Topaz Wichita, Kansas		3. Owner of well: R.R. or street: City, state, zip code:		
				Jon Lofgreen 4221 West 11th street Wichita, Kansas		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map:		6. Bore hole dia. 11 in. Completion date 6-6-77 Well depth 110 ft.		
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 110 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200		
5. Type and color of material		From	To	10. Screen: Manufacturer's name Sunflower Plastic		
Topsoil		0	3	Type Styrene Dia. 5"		
Brown Clay		3	18	Slot/.06 Length 30'		
Fine Sand		18	30	Set between 80 ft. and 110 ft.		
Gray Clay		30	32	Gravel pack? yes Size range of material 1/8"		
Fine Sand		32	70	11. Static water level: 35 ft. below land surface Date 6-6-77		
Medium Sand		70	110	12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.		
				13. Water sample submitted: mo./day/yr. Yes No Date		
				14. Well head completion: ☒ Pitless adapter 12 inches above grade		
				15. Well grouted? yes 1 to 2 fine With: sand mix ☒ Bentonite ☐ Concrete Depth: From 40" ft. to 14 ft.		
				16. Nearest source of possible contamination: City ft. 75 Direction West Type Sewer Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: Not installed Manufacturer's name Sta-Rite Model number 20P4E02 HP 1 Volts 230 Length of drop pipe 50 ft. capacity 25 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 6-15-77 Authorized representative		
Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5