


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

NE NW NW NW

1. Location of well:		County Sedgwick	Fraction 1/4 NW 1/4 NW 1/4	Section number 28	Township number 27 S	Range number R 1W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: 8605 West Maple Wichita, Kansas			3. Owner of well: R.R. or street: City, state, zip code: Church of God 8605 West Maple Wichita, Kansas			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 		6. Bore hole dia. 11 in. Completion date _____ Well depth 129 ft. 7-4-77	
5. Type and color of material			From	To	7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Topsoil			0	4	8. Use: Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other	
Brown Clay			4	16	9. Casing: Material Styrene Height: Above or below _____ Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight _____ lbs./ft. Dia. 5 in. to 129 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth Gauge No. .200	
Fine Sand			16	30	10. Screen: Manufacturer's name Sunflower Plastic	
Gray Clay			30	35	Type Styrene Dia. 5" Slot/gauge .06 Length 20' Set between 80 ft. and 90 ft. 119 ft. and 129 ft. Gravel pack? ☒ Yes Size range of material 1/4-1/8"	
Fine Sand			35	75	11. Static water level: _____ mo./day/yr. 30 ft. below land surface Date 7-4-77	
Medium Sand			75	90	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
Fine Sand			90	95	13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☐ No Date _____	
Gray Clay			95	100	14. Well head completion: ☒ Pitless adapter 12 inches above grade	
Fine Sand			100	105	15. Well grouted? ☒ Yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
Gray Clay			105	114	16. Nearest source of possible contamination: City ft. 25 Direction West Type Sewer Well disinfected upon completion? ☒ Yes ☐ No	
Medium Sand			114	129	17. Pump: Not installed Manufacturer's name Sta-Rite Model number 20P4D02 HP 3/4 Volts 230 Length of drop pipe 60 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 8-31-77 Authorized representative		
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5